



VERIFICATION OF COMPLIANCE

This Verification of Compliance is hereby issued to the product designated below.

Product	Panel PC
Model	PPC-L61; PPC-L61T; PPC-L61XXXXXXXXXXXXXXXXXX (X = 0 - 9; A - Z or Blank)
Trade name	ADVANTECH
Applicant	Advantech Co. Ltd. No.1, Alley 20, Lane 26, Rueiguang Road, Neihu District, Taipei 114, Taiwan, R.O.C.
Applicable Standard(s)	EN 55022: 2006 + A1: 2007 EN 55011: 2007 + A2: 2007, Group 1 EN 61000-6-3: 2007 EN 61000-3-2: 2006 EN 61000-3-3: 2008 EN 55024: 1998 + A1: 2001 + A2: 2003 EN 61000-6-1: 2007 IEC 61000-4-2: 2008; IEC 61000-4-3: 2006 + A1: 2007; IEC 61000-4-4: 2004; IEC 61000-4-5: 2005; IEC 61000-4-6: 2008; IEC 61000-4-8: 2001; IEC 61000-4-11: 2004
Report No.	T100608102-E
Test Laboratory	Compliance Certification Services Inc. No. 81-1, Lane 210, Pa-De 2nd Rd., Luchu Hsiang, Taoyuan Shien, (338) Taiwan, R.O.C. Tel: +886-3-3240332/ Fax: +886-3-3245235

This device has been tested and found to comply with the stated standard(s), which is(are) required by the Council Directive of 2004/108/EC. The test results are indicated in the test report and are applicable only to the tested sample identified in the report.

Ethan Huang / Section Manager of Linkou Laboratory
Date: June 19, 2010



Compliance Certification Services Inc.



CE EMC TEST REPORT

for

Panel PC

**Model: PPC-L61; PPC-L61T;
PPC-L61XXXXXXXXXXXXXXXXXX (X = 0 - 9; A - Z or Blank)**

Test Report Number:
T100608102-E

Issued for

Advantech Co. Ltd.

No. 1, Alley 20, Lane 26, Rueiguang Road, Neihu District, Taipei 114, Taiwan, R.O.C.

Issued By:

Compliance Certification Services Inc.

Linkuo Laboratory

No. 81-1, Lane 210, Pa-De 2nd Rd., Luchu Hsiang,
Taoyuan Shien, (338), Taiwan, R.O.C.

TEL: 886-3-324-0332

FAX: 886-3-324-5235

E-Mail: service@ccsrf.com

Issued Date: June 19, 2010



Note: This report shall not be reproduced except in full, without the written approval of Compliance Certification Services Inc. This document may be altered or revised by Compliance Certification Services Inc. personnel only, and shall be noted in the revision section of the document. The client should not use it to claim product endorsement by TAF, A2LA, NIST or any government agencies. The test results in the report only apply to the tested sample.



Revision History

Rev.		Issue Date		Revisions	Effect Page	Revised By
00		June 19, 2010		Initial Issue	ALL	Celine Chou

TABLE OF CONTENTS

1	TEST CERTIFICATION.....	4
2	TEST RESULT SUMMARY.....	5
3	EUT DESCRIPTION.....	7
4	TEST METHODOLOGY.....	8
	4.1. DECISION OF FINAL TEST MODE.....	8
	4.2. EUT SYSTEM OPERATION.....	8
5	SETUP OF EQUIPMENT UNDER TEST.....	9
	5.1. DESCRIPTION OF SUPPORT UNITS.....	9
	5.2. CONFIGURATION OF SYSTEM UNDER TEST.....	9
6	FACILITIES AND ACCREDITATIONS.....	10
	6.1. FACILITIES.....	10
	6.2. ACCREDITATIONS.....	10
	6.3. MEASUREMENT UNCERTAINTY.....	11
7	EMISSION TEST.....	12
	7.1. CONDUCTED EMISSION MEASUREMENT.....	12
	7.2. CONDUCTED EMISSION MEASUREMENT AT TELECOMMUNICATION PORTS.....	17
	7.3. RADIATED EMISSION MEASUREMENT.....	20
	7.4. HARMONICS CURRENT MEASUREMENT.....	31
	7.5. VOLTAGE FLUCTUATION AND FLICKS MEASUREMENT.....	33
8	IMMUNITY TEST.....	38
	8.1. GENERAL DESCRIPTION.....	38
	8.2. GENERAL PERFORMANCE CRITERIA DESCRIPTION.....	40
	8.3. ELECTROSTATIC DISCHARGE (ESD).....	41
	8.4. RADIATED, RADIO-FREQUENCY, ELECTROMAGNETIC FIELD (RS).....	45
	8.5. ELECTRICAL FAST TRANSIENT (EFT).....	52
	8.6. SURGE IMMUNITY TEST.....	55
	8.7. CONDUCTED RADIO FREQUENCY DISTURBANCES (CS).....	58
	8.8. POWER FREQUENCY MAGNETIC FIELD.....	61
	8.9. VOLTAGE DIP & VOLTAGE INTERRUPTIONS.....	64
9	PHOTOGRAPHS OF THE TEST CONFIGURATION.....	67



1 TEST CERTIFICATION

Product:	Panel PC	
Model:	PPC-L61; PPC-L61T; PPC-L61XXXXXXXXXXXXXXXXXX (X = 0 - 9; A - Z or Blank)	
Brand:	ADVANTECH	
Applicant:	Advantech Co. Ltd. No.1, Alley 20, Lane 26, Rueiguang Road, Neihu District, Taipei 114, Taiwan, R.O.C.	
Manufacturer:	Advantech Co. Ltd. No.1, Alley 20, Lane 26, Rueiguang Road, Neihu District, Taipei 114, Taiwan, R.O.C.	
Tested:	June 9 ~ 14, 2010	
Test Voltage:	230VAC, 50Hz	
Applicable Standards:	EN 55022: 2006 +A1: 2007, Class B EN 55011: 2007 + A2: 2007, Group 1 EN 61000-6-3: 2007 EN 61000-3-2: 2006, Class D EN 61000-3-3: 2008	EN 55024: 1998 + A1: 2001 + A2: 2003 EN 61000-6-1: 2007 IEC 61000-4-2: 2008 IEC 61000-4-3: 2006 + A1: 2007 IEC 61000-4-4: 2004 IEC 61000-4-5: 2005 IEC 61000-4-6: 2008 IEC 61000-4-8: 2001 IEC 61000-4-11:2004

Deviation from Applicable Standard

According to manufacturer defined, all the test standards on this report are required to perform for this EUT.

The above equipment has been tested by Compliance Certification Services Inc., and found compliance with the requirements set forth in the technical standards mentioned above. The results of testing in this report apply only to the product/system, which was tested. Other similar equipment will not necessarily produce the same results due to production tolerance and measurement uncertainties.

Approved by:

Ethan Huang
Section Manager

Reviewed by:

Stan Lin
Supervisor

2 TEST RESULT SUMMARY

EMISSION 【EN 55022: 2006 + A1: 2007; EN 61000-6-3: 2007; EN 55011: 2007 + A2: 2007】			
Standard	Item	Result	Remarks
EN 55022: 2006 + A1: 2007 EN 55011: 2007 + A2: 2007 EN 61000-6-3: 2007	Conducted (Main Port)	PASS	Meet Class B limit
	Conducted (Telecommunication port)	PASS	Meet Class B limit
	Radiated	PASS	Meet Class B limit
EN 61000-3-2: 2006	Harmonic current emissions	PASS	Meet Class D limit
EN 61000-3-3: 2008	Voltage fluctuations & flicker	PASS	Meets the requirements

IMMUNITY 【EN 55024(1998 + A1: 2001 + A2: 2003)】			
Standard	Item	Result	Remarks
IEC 61000-4-2: 2008	ESD	PASS	Meets the requirements of Performance Criterion B
IEC 61000-4-3: 2006 + A1: 2007	RS	PASS	Meets the requirements of Performance Criterion A
IEC 61000-4-4: 2004	EFT	PASS	Meets the requirements of Performance Criterion B
IEC 61000-4-5: 2005	Surge	PASS	Meets the requirements of Performance Criterion B
IEC 61000-4-6: 2008	CS	PASS	Meets the requirements of Performance Criterion A
IEC 61000-4-8: 2001	PFMF	PASS	Meets the requirements of Performance Criterion A
IEC 61000-4-11:2004	Voltage dips & voltage variations	PASS	Meets the requirements of Voltage Dips: 1) >95% reduction Performance Criterion B 2) 30% reduction Performance Criterion C Voltage Interruptions: 1). >95% reduction Performance Criterion C



IMMUNITY 【EN 61000-6-1: 2007】			
Standard	Item	Result	Remarks
IEC 61000-4-2: 2008	ESD	PASS	Meets the requirements of Performance Criterion B
IEC 61000-4-3: 2006 + A1: 2007	RS	PASS	Meets the requirements of Performance Criterion A
IEC 61000-4-4: 2004	EFT	PASS	Meets the requirements of Performance Criterion B
IEC 61000-4-5: 2005	Surge	PASS	Meets the requirements of Performance Criterion B
IEC 61000-4-6: 20098	CS	PASS	Meets the requirements of Performance Criterion A
IEC 61000-4-8: 2001	PFMF	PASS	Meets the requirements of Performance Criterion A
IEC 61000-4-11:2004	Voltage dips & voltage variations	PASS	Meets the requirements of Voltage Dips: 1) 30% reduction Performance Criterion B 2) 60% reduction Performance Criterion C Voltage Interruptions: 1) >95% reduction Performance Criterion C

- Note:**
1. The statements of test result on the above are decided by the request of test standard only; the measurement uncertainties are not factored into this compliance determination.
 2. The information of measurement uncertainty is available upon the customer's request.



3 EUT DESCRIPTION

Product	Panel PC		
Brand Name	ADVANTECH		
Model	PPC-L61; PPC-L61T; PPC-L61XXXXXXXXXXXXXXXXXX (X = 0 - 9; A - Z or Blank)		
Applicant	Advantech Co. Ltd.		
Serial Number	T100608102		
Received Date	June 8, 2010		
EUT Power Rating	12-30VDC, 2.5A		
DC Power Cable Type	1.8m (Detachable)		
Power Adapter Manufacturer	SINPRO	Model	SPU-60-107
Power Adapter Power Rating	I/P: 100-240VAC, 47-63Hz, 1.6A O/P: 19VDC, 3.15A		
CPU Manufacturer	AMD	Model	ALXD 800 EEXJ2VD
Memory Manufacturer	512MB		
Main Board Manufacturer	ADVANTECH	Model	PCM-9697
6.5" LED Panel Manufacturer	AUO	Model	G065VN01 V2
SATA to IDE Card Manufacturer	ADVANTECH	Model	PCM-071
CF Card Manufacturer	SQFlash	Model	SQF-P10S2-2G-CTE (2GB)
LAN Manufacturer	On Board		

I/O PORT OF EUT

I/O PORT TYPES	Q'TY	TESTED WITH
1. RS-232 Port	2	2
2. D-SUB Port	1	1
3. USB Port	2	2
4. LAN Port	1	1

Note: 1. All the model numbers are identical just for marketing purpose only

2. The mean of "X (X = 0 - 9; A - Z or Blank)" on model number, they are identical just for marketing purpose only.

3. Client consigns only one sample to test (model number: PPC-L61T). Therefore, the testing Lab. just guarantees the unit, which has been tested.

4 TEST METHODOLOGY

4.1. DECISION OF FINAL TEST MODE

1. The following test mode(s) were scanned during the preliminary test:

Pre-Test Mode
Mode 1: 640 x 480, 60Hz

2. After the preliminary scan, the following test mode was found to produce the highest emission level.

Final Test Mode		
Emission	Conducted Emission	Mode 1
	Radiated Emission	Mode 1
Immunity		Mode 1

Then, the above highest emission mode of the configuration of the EUT and cable was chosen for all final test items.

4.2. EUT SYSTEM OPERATION

1	Setup the EUT and simulators as shown on 5.2.
2	Turn on the power of all equipment.
3	EMI test program (file name: EMCTEST. EXE) was loaded and executed in "Windows XP" mode.
4	Data was sent to monitor and filling the screen with upper case of "H" patterns.
5	Test program sequentially exercised all related I/O's and accessories of EUT and sent "H" patterns to all applicable output ports of EUT.
6	EUT Connect Notebook Computer at remote side through LAN port, and carry out Read/Write work each other.
7	Repeat 3 to 6.

Note: Test program is self-repeating throughout the test.

5 SETUP OF EQUIPMENT UNDER TEST

5.1. DESCRIPTION OF SUPPORT UNITS


The EUT has been tested as an independent unit together with other necessary accessories or support units. The following support units or accessories were used to form a representative test configuration during the tests.

No.	Equipment	Model No.	Serial No.	FCC ID	Trade Name	Data Cable	Power Cord
1	LCD Monitor	2408WFB	CN-0G293H-74261-874-2CWS	FCC DoC	DELL	D-SUB Cable: Shielded, 1.8m with two cores	Unshielded, 1.8m
2	Modem	DM-1414	304012264	IFAXDM1414	ACEEX	Unshielded, 1.8m	Unshielded, 1.8m
3	Modem	DM-1414	304012261	IFAXDM1414	ACEEX	Unshielded, 1.8m	Unshielded, 1.8m
4	USB Keyboard	6512-UV	21200201-12937808 65	FCC DoC	ACER	USB Cable: Shielded, 1.8m	N/A
5	USB Mouse	MO19UCA	020509272	FCC DoC	HP	USB Cable: Shielded, 1.8m	N/A
6	Notebook PC (Remote)	COMPAQ NC 4010	CNU5191L58	FCC DOC	HP	LAN Cable: Unshielded, 10m	AC I/P: Unshielded, 1.8m DC O/P: Unshielded, 1.8m with a core

Note: Grounding was established in accordance with the manufacturer's requirements and conditions for the intended use.

5.2. CONFIGURATION OF SYSTEM UNDER TEST

1. LCD Monitor	2. Modem	3. Modem
4. USB Keyboard	5. USB Mouse	6. Notebook PC





6 FACILITIES AND ACCREDITATIONS

6.1. FACILITIES

All measurement facilities used to collect the measurement data are located at No. 81-1, Lane 210, Pa-De 2nd Rd., Luchu Hsiang, Taoyuan Shien, Taiwan.

The sites are constructed in conformance with the requirements of ANSI C63.4 and CISPR 22. All receiving equipment conforms to CISPR 16-1-1, CISPR 16-1-2, CISPR 16-1-3, CISPR 16-1-4, CISPR 16-1-5 and CISPR 16-2-3.

6.2. ACCREDITATIONS

Our laboratories are accredited and approved by the following approval agencies according to ISO/IEC 17025.

Taiwan	TAF
USA	A2LA

The measuring facility of laboratories has been authorized or registered by the following approval agencies.

Canada	Industry Canada
Norway	Nemko
Japan	VCCI
Taiwan	BSMI
USA	FCC

Copies of granted accreditation certificates are available for downloading from our web site, <http://www.ccsrf.com>

6.3. MEASUREMENT UNCERTAINTY

Where relevant, the following measurement uncertainty levels have been estimated for tests performed on the EUT as specified in CISPR 16-4-2:

Measurement	Frequency	Uncertainty
Conducted emissions	9kHz~30MHz	± 1.7983
Radiated emissions	30~200MHz	± 3.8881
	200~1000MHz	± 3.8724

This uncertainty represents an expanded uncertainty expressed at approximately the 95% confidence level using a coverage factor of $k=2$.

Consistent with industry standard (e.g. CISPR 22: 2006, clause 11, Measurement Uncertainty) determining compliance with the limits shall be based on the results of the compliance measurement. Consequently the measured emissions being less than the maximum allowed emission result in this being a compliant test or passing test.

The acceptable measurement uncertainty value without requiring revision of the compliance statement is based on conducted and radiated emissions being less than U_{CISPR} which is 3.6dB and 5.2dB respectively. CCS values (called U_{Lab} in CISPR 16-4-2) is less than U_{CISPR} as shown in the table above. Therefore, MU need not be considered for compliance.



7 EMISSION TEST

7.1. CONDUCTED EMISSION MEASUREMENT

7.1.1. LIMITS

FREQUENCY (MHz)	Class A (dBuV)(EN61000-6-3)		Class B (dBuV)(EN61000-6-3)	
	Quasi-peak	Average	Quasi-peak	Average
0.15 - 0.5	79	66	66 - 56	56 - 46
0.50 - 5.0	73	60	56	46
5.0 - 30.0	73	60	60	50

NOTE: 1. The lower limit shall apply at the transition frequencies.
2. The limit decreases in line with the logarithm of the frequency in the range 0.15 to 0.50 MHz.
3. All emanations from a class A/B digital device or system, including any network of conductors and apparatus connected thereto, shall not exceed the level of field strengths specified above.

7.1.2. TEST INSTRUMENTS

Conducted Emission Room # 4				
Name of Equipment	Manufacturer	Model	Serial Number	Calibration Due
EMI Test Receiver	R&S	ESCI	100782	06/01/2011
LISN	R&S	ENV216	100066	03/31/2011
LISN	R&S	ENV 4200	830326/016	04/27/2011
Test S/W	CCS-3A1-CE			

NOTE: 1. The calibration interval of the above test instruments is 12 months and the calibrations are traceable to NML/ROC and NIST/USA.
2. N.C.R = No Calibration Request.


7.1.3. TEST PROCEDURES (please refer to measurement standard or CCS SOP PA-031)**Procedure of Preliminary Test**

- The EUT and support equipment, if needed, were set up as per the test configuration to simulate typical usage per the user's manual. When the EUT is a tabletop system, a wooden table with a height of 0.8 meters is used and is placed on the ground plane as per EN 55022 (see Test Facility for the dimensions of the ground plane used). When the EUT is a floor standing equipment, it is placed on the ground plane, which has a 3-12 mm non-conductive covering to insulate the EUT from the ground plane.
- All I/O cables were positioned to simulate typical actual usage as per EN 55022.
- The EUT installed by AC main power, through a Line Impedance Stabilization Network (LISN), which was supplied power source and was grounded to the ground plane.
- All support equipment power by a second LISN.
- The test program of the EUT was started. Emissions were measured on each current carrying line of the EUT using an EMI Test Receiver connected to the LISN powering the EUT.
- The Receiver scanned from 150kHz to 30MHz for emissions in each of the test modes.
- During the above scans, the emissions were maximized by cable manipulation.
- The test mode(s) described in Item 3.1 were scanned during the preliminary test.
- After the preliminary scan, we found the test mode described in Item 3.1 producing the highest emission level.
- The worst configuration of EUT and cable of the above highest emission level were recorded for reference of the final test.

Procedure of Final Test

- EUT and support equipment were set up on the test bench as per the configuration with highest emission level in the preliminary test.
- A scan was taken on both power lines, Line 1 and Line 2, recording at least the six highest emissions. Emission frequency and amplitude were recorded into a computer in which correction factors were used to calculate the emission level and compare reading to the applicable limit.
- The test data of the worst-case condition(s) was recorded.

7.1.4. TEST SETUP



- For the actual test configuration, please refer to the related item – Photographs of the Test Configuration.

7.1.5. DATA SAMPLE:


Frequency (MHz)	QuasiPeak reading (dBuV)	Average reading (dBuV)	Correctrion factor (dB)	QuasiPeak result (dBuV)	Average result (dBuV)	QuasiPeak. limit (dBuV)	Average limit (dBuV)	QuasiPeak margin (dB)	Average margin (dB)	Remark
x.xx	43.95	33.00	10.00	53.95	43.00	56.00	46.00	-2.05	-3.00	Pass

Frequency (MHz)	= Emission frequency in MHz
Reading (dBuV)	= Uncorrected Analyzer/Receiver reading + Insertion loss of LISN, if it > 0.5 dB
Correction Factor (dB)	= LISN Factor + Cable loss
Result (dBuV)	= Raw reading converted to dBuV and CF added
Limit (dBuV)	= Limit stated in standard
Margin (dB)	= Result (dBuV) – Limit (dBuV)

7.1.6. TEST RESULTS

CCS Conduction Test 4

Model No.	PPC-L61T	6dB Bandwidth	9 kHz
Environmental Conditions	25°C, 57% RH	Test Mode	Mode 1
Tested by	Juicheng Su	Line	L1




NO.	Frequency	QuasiPeak reading	Average reading	Correction factor	QuasiPeak result	Average result	QuasiPeak limit	Average limit	QuasiPeak margin	Average margin	Remark
	(MHz)	(dBuV)	(dBuV)	(dB)	(dBuV)	(dBuV)	(dBuV)	(dBuV)	(dB)	(dB)	(Pass/Fail)
1*	0.1617	37.27	28.87	9.73	47.00	38.60	65.38	55.38	-18.38	-16.78	Pass
2	0.2125	31.78	26.28	9.72	41.50	36.00	63.11	53.11	-21.61	-17.11	Pass
3	7.3375	31.78	22.98	9.92	41.70	32.90	60.00	50.00	-18.30	-17.10	Pass
4	7.6070	32.15	22.55	9.95	42.10	32.50	60.00	50.00	-17.90	-17.50	Pass
5	13.2242	27.31	19.91	10.29	37.60	30.20	60.00	50.00	-22.40	-19.80	Pass
6	18.3492	26.40	19.90	10.40	36.80	30.30	60.00	50.00	-23.20	-19.70	Pass

REMARKS: L1 = Line One (Live Line)



CCS Conduction Test 4

Model No.	PPC-L61T	6dB Bandwidth	9 kHz
Environmental Conditions	25°C, 57% RH	Test Mode	Mode 1
Tested by	Juicheng Su	Line	L2



NO.	Frequency	QuasiPeak reading	Average reading	Correction factor	QuasiPeak result	Average result	QuasiPeak limit	Average limit	QuasiPeak margin	Average margin	Remark
	(MHz)	(dBuV)	(dBuV)	(dB)	(dBuV)	(dBuV)	(dBuV)	(dBuV)	(dB)	(dB)	(Pass/Fail)
1	0.1655	31.08	23.98	9.72	40.80	33.70	65.18	55.18	-24.38	-21.48	Pass
2	0.2164	26.99	25.29	9.71	36.70	35.00	62.95	52.96	-26.25	-17.96	Pass
3	6.6891	28.11	19.71	9.89	38.00	29.60	60.00	50.00	-22.00	-20.40	Pass
4*	7.2789	32.78	25.58	9.92	42.70	35.50	60.00	50.00	-17.30	-14.50	Pass
5	13.3219	29.55	22.85	10.35	39.90	33.20	60.00	50.00	-20.10	-16.80	Pass
6	17.5797	28.92	23.62	10.48	39.40	34.10	60.00	50.00	-20.60	-15.90	Pass

REMARKS: L2 = Line Two (Neutral Line)



7.2. CONDUCTED EMISSION MEASUREMENT AT TELECOMMUNICATION PORTS

7.2.1. LIMITS

For Class A Equipment

FREQUENCY (MHz)	Voltage Limit (dBuV)		Current Limit (dBuA)	
	Quasi-peak	Average	Quasi-peak	Average
0.15 ~ 0.5	97 ~ 87	84 ~ 74	53 ~ 43	40 ~ 30
0.5 ~ 30.0	87	74	43	30

For Class B Equipment

FREQUENCY (MHz)	Voltage Limit (dBuV)		Current Limit (dBuA)	
	Quasi-peak	Average	Quasi-peak	Average
0.15 - 0.5	84 ~ 74	74 ~ 64	40 ~ 30	30 ~ 20
0.5 - 30.0	74	64	30	20

NOTE: The limits decrease linearly with the logarithm of the frequency in the range 0.15 MHz to 0.5 MHz.

7.2.2. TEST INSTRUMENTS

Conducted Emission Room # 4				
Name of Equipment	Manufacturer	Model	Serial Number	Calibration Due
EMI Test Receiver	R&S	ESCI	100782	06/01/2011
LISN	R&S	ENV216	100066	03/31/2011
LISN	R&S	ENV 4200	830326/016	04/27/2011
ISN	FCC	FCC-TLISN-T4-02	20396	06/07/2011
ISN	TESEQ	ISN ST08	27907	09/24/2010
Current Probe	FCC	F-35	506	06/29/2010
Telecom ISN	FCC	FCC-TLISN-T2-PL C	20491	11/30/2010
Test S/W	CCS-3A1-CE			

NOTE: 1. The calibration interval of the above test instruments is 12 months and the calibrations are traceable to NML/ROC and NIST/USA.

2. N.C.R = No Calibration Request.




7.2.3. TEST PROCEDURE (please refer to measurement standard or CCS SOP PA-031)

- Selecting ISN for unscreened cable or a current probe for screened cable to take measurement.
- The port of the EUT was connected to the remote side support equipment through the ISN/Current Probe and communication in normal condition.
- Making a overall range scan by using the test receiver controlled by controller and record at least six highest emissions for showing in the test report.
- Emission frequency and amplitude were recorded into a computer in which correction factors were used to calculate the emission level and compare reading to the applicable limit.
- In case of measuring on the screened cable, the current limit shall be applied; otherwise the voltage limit should be applied.
- The following test mode was scanned during the preliminary test:
Mode 1: 10/100 Mbps (Emission mode 1)
- After the preliminary scan, we found the following test mode(s) producing the highest emission level and test data of the worst case was recorded.

Mode 1

7.2.4. TEST SETUP



- For the actual test configuration, please refer to the related item – Photographs of the Test Configuration.

7.2.5. DATA SAMPLE:


Frequency (MHz)	QuasiPeak reading (dBuV)	Average reading (dBuV)	Correction factor (dB)	QuasiPeak result (dBuV)	Average result (dBuV)	QuasiPeak limit (dBuV)	Average limit (dBuV)	QuasiPeak margin (dB)	Average margin (dB)	Remark
x.xx	43.95	33.00	10.00	53.95	43.00	84.00	74.00	-30.05	-31.00	Pass

Frequency (MHz) = Emission frequency in MHz
 Reading (dBuV) = Uncorrected Analyzer/Receiver reading + Insertion loss of LISN, if it > 0.5 dB
 Correction Factor (dB) = ISN Factor + Cable loss
 Result (dBuV) = Raw reading converted to dBuV and CF added
 Limit (dBuV) = Limit stated in standard
 Margin (dB) = Result (dBuV) – Limit (dBuV)

7.2.6. TEST RESULTS

CCS Conduction Test 4

Model No.	PPC-L61T	6dB Bandwidth	9 kHz
Environmental Conditions	25°C, 57% RH	Test Mode	Mode 1
Tested by	Juicheng Su	Line	10Mbps




NO.	Frequency	QuasiPeak reading	Average reading	Correction factor	QuasiPeak result	Average result	QuasiPeak limit	Average limit	QuasiPeak margin	Average margin	Remark
	(MHz)	(dBuV)	(dBuV)	(dB)	(dBuV)	(dBuV)	(dBuV)	(dBuV)	(dB)	(dB)	(Pass/Fail)
1	0.2164	59.86	58.36	10.04	69.90	68.40	80.95	70.96	-11.05	-2.56	Pass
2	0.2672	57.16	56.56	10.04	67.20	66.60	79.20	69.20	-12.00	-2.60	Pass
3	0.3219	55.36	53.06	10.04	65.40	63.10	77.66	67.66	-12.26	-4.56	Pass
4*	0.3766	55.37	54.27	10.03	65.40	64.30	76.35	66.35	-10.95	-2.05	Pass
5	0.4313	54.00	52.50	10.00	64.00	62.50	75.23	65.23	-11.23	-2.73	Pass
6	5.0289	34.70	32.80	10.15	44.85	42.95	74.00	64.00	-29.15	-21.05	Pass



CCS Conduction Test 4

Model No.	PPC-L61T	6dB Bandwidth	9 kHz
Environmental Conditions	25°C, 57% RH	Test Mode	Mode 1
Tested by	Juicheng Su	Line	100Mbps



NO.	Frequency	QuasiPeak reading	Average reading	Correction factor	QuasiPeak result	Average result	QuasiPeak limit	Average limit	QuasiPeak margin	Average margin	Remark
	(MHz)	(dBuV)	(dBuV)	(dB)	(dBuV)	(dBuV)	(dBuV)	(dBuV)	(dB)	(dB)	(Pass/Fail)
1	0.2164	59.56	58.86	10.04	69.60	68.90	80.96	70.96	-11.36	-2.06	Pass
2	0.2711	57.26	56.76	10.04	67.30	66.80	79.08	69.08	-11.78	-2.28	Pass
3	0.3219	54.76	51.76	10.04	64.80	61.80	77.66	67.66	-12.86	-5.86	Pass
4*	0.3766	55.37	54.27	10.03	65.40	64.30	76.35	66.35	-10.95	-2.05	Pass
5	0.4313	54.10	52.80	10.00	64.10	62.80	75.23	65.23	-11.13	-2.43	Pass
6	5.0250	53.65	46.45	10.15	63.80	56.60	74.00	64.00	-10.20	-7.40	Pass

7.3. RADIATED EMISSION MEASUREMENT

7.3.1. LIMITS

FREQUENCY (MHz)	dBuV/m (At 10m)	
	Class A	Class B (EN61000-6-3)
30 ~ 230	40	30
230 ~ 1000	47	37

NOTE: 1. The lower limit shall apply at the transition frequencies.
2. Emission level (dBuV/m) = 20 log Emission level (uV/m).

FREQUENCY (MHz)	dBuV/m (At 3m)	
	Average	Peak
1000 ~ 3000	50	70
3000 ~ 6000	54	74

NOTE: 1. The lower limit shall apply at the transition frequencies.

According to EN55022: 2006 + A1: 2007 clause 6.2, the measurement frequency range shown in the following table:

Highest frequency generated or used within the EUT or on which the EUT operates or tunes (MHz)	Upper frequency of measurement range (MHz)
Less than 108	1000
108-500	2000
500-1000	5000
Above 1000	5 times of the highest frequency or 6GHz, whichever is less

**7.3.2. TEST INSTRUMENTS**

Open Area Test Site # 2				
Name of Equipment	Manufacturer	Model	Serial Number	Calibration Due
Spectrum Analyzer	Agilent	E4411B	MY41440314	N.C.R
EMI Test Receiver	R&S	ESCS30	847793/012	05/18/2011
Pre-Amplifier	HP	8447D	2944A08780	08/07/2010
Bilog Antenna	CHASE	CBL 6112A	2307	06/11/2011
Turn Table	DCCS	CC-T-1F	N/A	N.C.R
Antenna Tower	CCS	CC-A-1F	N/A	N.C.R
Controller	CCS	CC-C-1F	N/A	N.C.R
RF Switch	ANRITSU	MP59B	M76890	N.C.R
Site NSA	CCS	N/A	N/A	05/08/2011
Test S/W	LabVIEW 6.1 (CCS OATS EMI SW V2.7)			

3 Meter Chamber				
Name of Equipment	Manufacturer	Model	Serial Number	Calibration Due
Spectrum Analyzer	Agilent	E4446A	MY48250064	11/05/2010
Pre-Amplifier	HP	8449B	3008A00965	04/17/2011
Pre-Amplifier	MITEQ	AMF-6F-260400-40-8P	985646	05/24/2011
Horn Antenna	EMCO	3115	9602-4659	04/16/2011
Horn Antenna	EMCO	3116	00026370	10/13/2010
Low Loss Cable	Huber+Suhner	104PEA	24813/4PEA	04/17/2011
Low Loss Cable	Huber+Suhner	104PEA	30956/4PEA	04/17/2011
Site VSWR	SIDT EUROPE	9x6x6	N/A	02/27/2011
Turn Table	CCS	CC-T-1F	N/A	N.C.R
Antenna Tower	CCS	CC-A-1F	N/A	N.C.R
Controller	CCS	CC-C-1F	N/A	N.C.R
Test S/W	CCS-3A1RE			

NOTE: 1. The calibration interval of the above test instruments is 12 months and the calibrations are traceable to NML/ROC and NIST/USA.
2. N.C.R = No Calibration Request.

7.3.3. TEST PROCEDURE (please refer to measurement standard or CCS SOP PA-031)**Procedure of Preliminary Test**


- The equipment was set up as per the test configuration to simulate typical usage per the user's manual. When the EUT is a tabletop system, a wooden turntable with a height of 0.8 meters is used which is placed on the ground plane. When the EUT is a floor standing equipment, it is placed on the ground plane which has a 3-12 mm non-conductive covering to insulate the EUT from the ground plane.
- Support equipment, if needed, was placed as per EN 55022.
- All I/O cables were positioned to simulate typical usage as per EN 55022.
- The EUT received AC power source from the outlet socket under the turntable. All support equipment power received from another socket under the turntable.
- The antenna was placed at 3 or 10 meter away from the EUT as stated in EN 55022. The antenna connected to the Spectrum Analyzer via a cable and at times a pre-amplifier would be used.
- The Analyzer / Receiver quickly scanned from 30MHz to 6000MHz. The EUT test program was started. Emissions were scanned and measured rotating the EUT to 360 degrees and positioning the antenna 1 to 4 meters above the ground plane, in both the vertical and the horizontal polarization, to maximize the emission reading level.
- The test mode(s) described in Item 3.1 were scanned during the preliminary test:
- After the preliminary scan, we found the test mode described in Item 3.1 producing the highest emission level.
- The worst configuration of EUT and cable, antenna position, polarization and turntable position of the above highest emission levels were recorded for the final test.

Procedure of Final Test


- EUT and support equipment were set up on the turntable as per the configuration with highest emission level in the preliminary test.
- The Analyzer / Receiver scanned from 30MHz to 6000MHz. Emissions were scanned and measured rotating the EUT to 360 degrees, varying cable placement and positioning the antenna 1 to 4 meters above the ground plane, in both the vertical and the horizontal polarization, to maximize the emission reading level.
- Recording at least the six highest emissions. Emission frequency, amplitude, antenna position, polarization and turntable position were recorded into a computer in which correction factors were used to calculate the emission level and compare reading to the applicable limit and only Q.P. reading is presented.
- The test data of the worst-case condition(s) was recorded.

7.3.4. TEST SETUP

Below 1GHz



Above 1GHz



- For the actual test configuration, please refer to the related item – Photographs of the Test Configuration.

**7.3.5. DATA SAMPLE:****Below 1GHz**

Frequency (MHz)	Reading (dBuV)	Correction Factor (dB/m)	Result (dBuV/m)	Limit (dBuV/m)	Margin (dB)	Degree (°)	Height (cm)	Remark
xx.xx	16.49	9.86	26.35	30.00	-3.65	116.00	101.00	QP

Above 1GHz

Frequency MHz	Corr. Factor (dB/m)	Reading		Result		Limit		Margin	
		Average (dBuV/m)	Peak (dBuV/m)	Average (dBuV/m)	Peak (dBuV/m)	Average (dBuV/m)	Peak (dBuV/m)	Average (dB)	Peak (dB)
xxxx.xxx	-4.35	49.81	58.74	45.46	54.39	54.00	74.00	-8.54	-19.61

Frequency (MHz) = Emission frequency in MHz

Reading (dBuV) = Uncorrected Analyzer / Receiver reading

Correction Factor (dB/m) = Antenna factor + Cable loss – Amplifier gain

Result (dBuV/m) = Reading (dBuV) + Corr. Factor (dB/m)

Limit (dBuV/m) = Limit stated in standard


Margin (dB) = Result (dBuV/m) – Limit (dBuV/m)

Q.P. = Quasi-Peak

7.3.6. TEST RESULTS

Below 1GHz


Model No.	PPC-L61T	Test Mode	Mode 1
Environmental Conditions	26°C, 60% RH	Test Frequency Range	30MHz ~ 1000MHz
Antenna Pole	Vertical	Antenna Distance	10m
Detector Function:	Quasi-peak.	Tested by	Louis Shen



No.	Frequency (MHz)	Reading (dBuV)	Correction Factor(dB/m)	Result (dBuV/m)	Limit (dBuV/m)	Margin (dB)	Degree (°)	Height (cm)	Remark
1	162.08	37.96	-15.11	22.86	30.00	-7.14	346.60	100.00	QP
2	182.38	38.89	-15.76	23.13	30.00	-6.87	0.00	100.00	QP
3	477.56	33.94	-5.93	28.02	37.00	-8.98	71.00	167.30	QP
4	525.30	32.29	-4.46	27.83	37.00	-9.17	221.80	167.30	QP
5	600.00	34.04	-3.26	30.78	37.00	-6.22	299.00	167.30	QP
6	643.00	30.21	-2.25	27.95	37.00	-9.05	74.10	167.30	QP
7	682.64	30.92	-2.16	28.76	37.00	-8.24	147.90	167.30	QP
8	710.10	31.24	-1.94	29.30	37.00	-7.70	152.30	100.00	QP
9	799.30	31.20	-0.20	31.00	37.00	-6.00	31.20	100.00	QP

REMARKS: The other emission levels were very low against the limit.

Model No.	PPC-L61T	Test Mode	Mode 1
Environmental Conditions	26°C, 60% RH	Test Frequency Range	30MHz ~ 1000MHz
Antenna Pole	Horizontal	Antenna Distance	10m
Detector Function:	Quasi-peak.	Tested by	Louis Shen



No.	Frequency (MHz)	Reading (dBuV)	Correction Factor(dB/m)	Result (dBuV/m)	Limit (dBuV/m)	Margin (dB)	Degree (°)	Height (cm)	Remark
1	162.35	36.24	-15.12	21.12	30.00	-8.88	354.90	400.00	QP
2	237.00	35.08	-12.34	22.74	37.00	-14.26	58.90	400.00	QP
3	498.25	34.00	-5.53	28.47	37.00	-8.53	293.30	171.70	QP
4	600.03	32.05	-3.26	28.79	37.00	-8.21	281.60	171.70	QP
5	634.40	32.35	-2.46	29.90	37.00	-7.10	143.80	171.70	QP
6	665.00	32.23	-2.12	30.11	37.00	-6.89	137.60	171.70	QP
7	687.40	32.32	-2.17	30.15	37.00	-6.85	218.70	171.70	QP
8	731.30	31.12	-1.39	29.73	37.00	-7.27	46.30	100.00	QP
9	798.13	28.30	-0.22	28.08	37.00	-8.92	205.30	100.00	QP

REMARKS: The other emission levels were very low against the limit.

Above 1GHz

Model No.	PPC-L61T	Test Mode	Mode 1
Environmental Conditions	18°C, 60% RH	6dB Bandwidth	1 MHz
Antenna Pole	Vertical	Antenna Distance	3m
Highest frequency generated or used	504MHz	Upper frequency	6000MHz
Detector Function:	Peak/Average	Tested By	Han Chaic

Frequency MHz	Corr. Factor (dBuV/m)	Reading		Result		Limit		Margin	
		Average (dBuV/m)	Peak (dBuV/m)	Average (dBuV/m)	Peak (dBuV/m)	Average (dBuV/m)	Peak (dBuV/m)	Average (dB)	Peak (dB)
1190.885	-8.51	--	53.24	--	44.73	50.00	70.00	--	-25.27
1362.169	-7.53	--	51.78	--	44.25	50.00	70.00	--	-25.75
1450.329	-7.04	--	51.88	--	44.84	50.00	70.00	--	-25.16
1798.227	-4.91	--	50.15	--	45.24	50.00	70.00	--	-24.76
1880.608	-4.40	--	50.10	--	45.70	50.00	70.00	--	-24.30
2141.481	-3.17	--	48.98	--	45.81	50.00	70.00	--	-24.19

REMARKS:

1. The other emission levels were very low against the limit.
2. "--", means the average measurement was not performed when the measured peak data under the limit of average detection.

Model No.	PPC-L61T	Test Mode	Mode 1
Environmental Conditions	18°C, 60% RH	6dB Bandwidth	1 MHz
Antenna Pole	Horizontal	Antenna Distance	3m
Highest frequency generated or used	504MHz	Upper frequency	6000MHz
Detector Function:	Peak/Average	Tested By	Han Chaic

Frequency MHz	Corr. Factor (dBuV/m)	Reading		Result		Limit		Margin	
		Average (dBuV/m)	Peak (dBuV/m)	Average (dBuV/m)	Peak (dBuV/m)	Average (dBuV/m)	Peak (dBuV/m)	Average (dB)	Peak (dB)
1196.231	-8.49	--	54.10	--	45.61	50.00	70.00	--	-24.39
1399.276	-7.32	--	51.61	--	44.29	50.00	70.00	--	-25.71
1644.133	-5.86	--	50.53	--	44.67	50.00	70.00	--	-25.33
1806.300	-4.86	--	48.97	--	44.11	50.00	70.00	--	-25.89
1993.371	-3.70	--	48.00	--	44.30	50.00	70.00	--	-25.70
2449.490	-2.09	--	48.08	--	45.99	50.00	70.00	--	-24.01

REMARKS:

1. The other emission levels were very low against the limit.
2. "--", means the average measurement was not performed when the measured peak data under the limit of average detection.



7.4. HARMONICS CURRENT MEASUREMENT

7.4.1. LIMITS OF HARMONICS CURRENT MEASUREMENT

Limits for Class A equipment		Limits for Class D equipment		
Harmonics Order n	Max. permissible harmonics current A	Harmonics Order n	Max. permissible harmonics current per watt mA/W	Max. permissible harmonics current A
Odd harmonics		Odd Harmonics only		
3	2.30	3	3.4	2.30
5	1.14	5	1.9	1.14
7	0.77	7	1.0	0.77
9	0.40	9	0.5	0.40
11	0.33	11	0.35	0.33
13	0.21	13	0.30	0.21
15<=n<=39	0.15x15/n	15<=n<=39	3.85/n	0.15x15/n
Even harmonics				
2	1.08			
4	0.43			
6	0.30			
8<=n<=40	0.23x8/n			

NOTE: 1. Class A and Class D are classified according to item 7.4.3.

2. According to section 7 of EN 61000-3-2, the above limits for all equipment except for lighting equipment having an active input power > 75 W and no limits apply for equipment with an active input power up to and including 75 W.

7.4.2. TEST INSTRUMENTS

Immunity Shielded Room				
Name of Equipment	Manufacturer	Model	Serial Number	Calibration Due
HARMONICS SYSTEM	EMC-PARTNER	HARMONICS-1000	094	01/18/2011
Test S/W	HARCS Immunity (4.10)			

NOTE: The calibration interval of the above test instruments is 12 months and the calibrations are traceable to NML/ROC and NIST/USA.

7.4.3. TEST PROCEDURE (please refer to measurement standard or CCS SOP PA-029)

- The EUT was placed on the top of a wooden table 0.8 meters above the ground and operated to produce the maximum harmonic components under normal operating conditions for each successive harmonic component in turn.
- The classification of EUT is according to section 5 of EN 61000-3-2.
- The EUT is classified as follows:


Class A: Balanced three-phase equipment, Household appliances excluding equipment as Class D, Tools excluding portable tools, Dimmers for incandescent lamps, audio equipment, equipment not specified in one of the three other classes.

Class B: Portable tools; Arc welding equipment which is not professional equipment.

Class C: Lighting equipment.

Class D: Equipment having a specified power less than or equal to 600 W of the following types: Personal computers and personal computer monitors and television receivers.

- The correspondent test program of test instrument to measure the current harmonics emanated from EUT is chosen. The measure time shall be not less than the time necessary for the EUT to be exercised.

7.4.4. TEST SETUP

- For the actual test configuration, please refer to the related item – Photographs of the Test Configuration.

7.4.5. TEST RESULTS

EUT max Power: 17.14W

Note: According to clause 7 of EN 61000-3-2, equipment with a rated power of 75W or less, no limits apply.



7.5. VOLTAGE FLUCTUATION AND FLICKS MEASUREMENT

7.5.1. LIMITS OF VOLTAGE FLUCTUATION AND FLICKS MEASUREMENT

TEST ITEM	LIMIT	REMARK
P_{st}	1.0	P_{st} means short-term flicker indicator.
P_{lt}	0.65	P_{lt} means long-term flicker indicator.
T_{dt} (ms)	500	T_{dt} means maximum time that dt exceeds 3.3 %.
d_{max} (%)	4%	d_{max} means maximum relative voltage change.
dc (%)	3.3%	dc means relative steady-state voltage change


7.5.2. TEST INSTRUMENTS

Immunity Shielded Room				
Name of Equipment	Manufacturer	Model	Serial Number	Calibration Due
HARMONICS SYSTEM	EMC-PARTNER	HARMONICS-1000	094	01/18/2011
Test S/W	HARCS Immunity (4.10)			

NOTE: The calibration interval of the above test instruments is 12 months and the calibrations are traceable to NML/ROC and NIST/USA.

7.5.3. TEST PROCEDURE (please refer to measurement standard or CCS SOP PA-030)

- The EUT was placed on the top of a wooden table 0.8 meters above the ground and operated to produce the most unfavorable sequence of voltage changes under normal operating conditions.
- During the flick measurement, the measure time shall include that part of whole operation cycle in which the EUT produce the most unfavorable sequence of voltage changes. The observation period for short-term flicker indicator is 10 minutes and the observation period for long-term flicker indicator is 2 hours.

7.5.4. TEST SETUP

- For the actual test configuration, please refer to the related item – Photographs of the Test Configuration.

7.5.5. TEST RESULTS

Observation Period (Tp)	10mins	Test Mode	Mode 1
Environmental Conditions	24°C, 44% RH	Tested by	Louis Shen

Power Continuity

TEST PARAMETER	MEASUREMENT VALUE	LIMIT	REMARK
P _{st}	0.072	1.0	PASS
P _{lt}	0.072	0.65	PASS
T _{dt} (ms)	0	500	PASS
d _{max} (%)	0%	4%	PASS
dc (%)	0.02%	3.3%	PASS

Power Switched Manually

TEST PARAMETER	MEASUREMENT VALUE	LIMIT	REMARK
P _{st}	0.072	1.0	PASS
P _{lt}	0.072	0.65	PASS
T _{dt} (ms)	0	500	PASS
d _{max} (%)	0.1%	4%	PASS
dc (%)	0.18%	3.3%	PASS

Note: d_{max} (%) limit classified:

1. 6% for equipment which is switched manually or switched automatically more frequently than twice per day.
2. 7% for equipment which is attended whilst use or switched on automatically no more than twice per day



ADVANTECH

Date : 2010/6/14 PM 07:37 V4.17

Operator : Louis Shen
Unit : Panel PC
Serialnumber : PPC-L61T
Remarks : Temp:24 Hemid:44 (Power Continuity)

Urms = 229.9V Freq = 50.000 Range: 1 A
Irms = 0.167A Ipk = 0.752A cf = 4.503
P = 16.69W S = 38.39VA pf = 0.435

Test - Time : 1 x 10min = 10min (100 %)

LIN (Line Impedance Network) : L: 0.24ohm +j0.15ohm N: 0.16ohm +j0.10ohm

Limits : Plt : 0.65 Pst : 1.00
dmax : 4.00 % dc : 3.30 %
dtLim: 3.30 % dt>Lim: 500ms

Test completed, Result: PASSED

Plt = 0.072

	Pst	dmax	dc	dt>Lim	Fail
		[%]	[%]	[ms]	
1	0.072	0.000	0.020	0.000	



ADVANTECH

Date : 2010/6/14 PM 07:50 V4.17

Operator : Louis Shen
Unit : Panel PC
Serialnumber : PPC-L61T
Remarks : Temp:24 Hemid:44 (Power Switched Manually)

Urms = 229.9V Freq = 50.000 Range: 1 A
Irms = 0.183A Ipk = 0.804A cf = 4.401
P = 18.11W S = 41.99VA pf = 0.431

Test - Time : 1 x 10min = 10min (100 %)

LIN (Line Impedance Network) : L: 0.24ohm +j0.15ohm N: 0.16ohm +j0.10ohm

Limits : Plt : 0.65 Pst : 1.00
dmax : 4.00 % dc : 3.30 %
dtLim: 3.30 % dt>Lim: 500ms

Test completed, Result: PASSED

Plt = 0.072

	Pst	dmax	dc	dt>Lim	Fail
		[%]	[%]	[ms]	
1	0.072	0.100	0.180	0.000	

8 IMMUNITY TEST

8.1. GENERAL DESCRIPTION

Product Standard	EN 55024: 1998 + A1: 2001 + A2: 2003; EN 61000-6-1: 2007	
	Test Type	Minimum Requirement
Basic Standard, Specification, and Performance Criterion required	IEC 61000-4-2	Electrostatic Discharge – ESD: 8kV air discharge, 4kV Contact discharge, Performance Criterion B
	IEC 61000-4-3	Radio-Frequency Electromagnetic Field Susceptibility Test – RS: For EN 55024: 80 ~1000 MHz, 3V/m, 80% AM(1kHz), For EN 61000-6-1: 80 ~1000 MHz, 3V/m, 80% AM (1kHz), 1400 ~2000 MHz, 3V/m, 80% AM (1kHz), 2000 ~ 2700 MHz, 1V/m, 80% AM (1kHz), Performance Criterion A
	IEC 61000-4-4	Electrical Fast Transient/Burst - EFT, AC Power Port: 1kV DC Power Port: 0.5kV Signal Ports and Telecommunication Ports: 0.5kV Performance Criterion B
	IEC 61000-4-5	Surge Immunity Test: 1.2/50 us Open Circuit Voltage 8/20 μs Short Circuit Current For EN 55024: AC Power Port ~ line to line: 1kV, line to earth (ground): 2kV DC Power Port ~ line to earth: 0.5kV Signal Ports and Telecommunication Ports ~ line to ground: 1kV Performance Criterion B For EN 61000-6-1: AC Power Port ~ line to line: 1kV, line to earth: 2kV DC Power Port ~ line to earth: 0.5kV, line to line: 0.5kV Performance Criterion B
	IEC 61000-4-6	Conducted Radio Frequency Disturbances Test –CS: 0.15 ~ 80 MHz, 3Vrms, 80% AM, 1kHz, Performance Criterion A

Product Standard	EN 55024: 1998 + A1: 2001 + A2: 2003; EN 61000-6-1: 2007	
	Test Type	Minimum Requirement
Basic Standard, Specification, and Performance Criterion required	IEC 61000-4-8	Power frequency magnetic field immunity test For EN 55024: 50 Hz, 1A/m For EN 61000-6-1: 50/60 Hz, 3A/m Performance Criterion A
	IEC 61000-4-11	For EN 55024: Voltage Dips: i) >95% reduction for 0.5 period, Performance Criterion B ii) 30% reduction for 25 period, Performance Criterion C Voltage Interruptions: >95% reduction for 250 period Performance Criterion C For EN 61000-6-1: Voltage Dips: i) 30% reduction for 0.5 period, Performance Criterion B ii) 60% reduction for 5 period, Performance Criterion C Voltage Interruptions: >95% reduction for 250 period Performance Criterion C

8.2. GENERAL PERFORMANCE CRITERIA DESCRIPTION

Criteria A:	The apparatus shell continues to operate as intended without operator intervention. No degradation of performance or loss of function is allowed below a performance level specified by the manufacturer, when the apparatus is used as intended. The performance level may be replaced by a permissible loss of performance. If the manufacturer does not specify the minimum performance level or the permissible performance loss, then either of these may be derived from the product description and documentation, and by what the user may reasonably expect from the equipment if used as intended.
Criteria B:	<p>After test, the apparatus shell continues to operate as intended without operator intervention. No degradation of performance or loss of function is allowed, after the application of the phenomenon below a performance level specified by the manufacturer, when the apparatus is used as intended. The performance level may be replaced by a permissible loss of performance.</p> <p>During the test, degradation of performance is however allowed. However, no change of operating state if stored data is allowed to persist after the test. If the manufacturer does not specify the minimum performance level or the permissible performance loss, then either of these may be derived from the product description and documentation, and by what the user may reasonably expect from the equipment if used as intended.</p>
Criteria C:	<p>Temporary loss of function is allowed, provided the functions is self-recoverable or can be restored by the operation of controls by the user in accordance with the manufacturer instructions.</p> <p>Functions, and/or information stored in non-volatile memory, or protected by a battery backup, shall not be lost.</p>



8.3. ELECTROSTATIC DISCHARGE (ESD)

8.3.1. TEST SPECIFICATION

Basic Standard:	IEC 61000-4-2
Discharge Impedance:	330 ohm / 150 pF
Discharge Voltage:	Air Discharge: 2; 4; 8 kV (Direct) Contact Discharge: 2; 4 kV (Direct/Indirect)
Polarity:	Positive & Negative Air Discharge: min. 10 times at single test point for each negative and positive polarity
Number of Discharge:	Contact Discharge: min. 200 times in total
Discharge Mode:	Single Discharge 1 second minimum

8.3.2. TEST INSTRUMENT

Immunity Shielded Room				
Name of Equipment	Manufacturer	Model	Serial Number	Calibration Due
ESD Generator	EM TEST	P30C	V0628101604	03/29/2011

NOTE: The calibration interval of the above test instruments is 12 months and the calibrations are traceable to NML/ROC and NIST/USA.

8.3.3. TEST PROCEDURE (please refer to measurement standard or CCS SOP PA-022)

The discharges shall be applied in two ways:

a) Contact discharges to the conductive surfaces and coupling planes:

The EUT shall be exposed to at least 200 discharges, 100 each at negative and positive polarity, at a minimum of four test points. One of the test points shall be subjected to at least 50 indirect discharges to the center of the front edge of the **Horizontal Coupling Plane (HCP)**. The remaining three test points shall each receive at least 50 direct contact discharges. If no direct contact test points are available, then at least 200 indirect discharges shall be applied in the indirect mode. Test shall be performed at a maximum repetition rate of one discharge per second.


b) Air discharges at slots and apertures and insulating surfaces:

On those parts of the EUT where it is not possible to perform contact discharge testing, the equipment should be investigated to identify user accessible points where breakdown may occur. Such points are tested using the air discharge method. This investigation should be restricted to those area normally handled by the user. A minimum of 10 single air discharges shall be applied to the selected test point for each such area.

The basic test procedure was in accordance with IEC 61000-4-2:

- a) The EUT was located 0.1 m minimum from all side of the **HCP** (dimensions 1.6m x 0.8m).
- b) The support units were located another table 30 cm away from the EUT, but direct support unit was/were located at same location as EUT on the HCP and keep at a distance of 10 cm with EUT.
- c) The time interval between two successive single discharges was at least 1 second.
- d) Contact discharges were applied to the non-insulating coating, with the pointed tip of the generator penetrating the coating and contacting the conducting substrate.
- e) Air discharges were applied with the round discharge tip of the discharge electrode approaching the EUT as fast as possible (without causing mechanical damage) to touch the EUT. After each discharge, the ESD generator was removed from the EUT and re-triggered for a new single discharge. The test was repeated until all discharges were complete.
- f) At least ten single discharges (in the most sensitive polarity) were applied at the front edge of each **HCP** opposite the center point of each unit of the EUT and 0.1 meters from the front of the EUT. The long axis of the discharge electrode was in the plane of the **HCP** and perpendicular to its front edge during the discharge.
- g) At least ten single discharges (in the most sensitive polarity) were applied to the center of one vertical edge of the **Vertical Coupling Plane (VCP)** in sufficiently different positions that the four faces of the EUT were completely illuminated. The **VCP** (dimensions 0.5m x 0.5m) was placed vertically to and 0.1 meters from the EUT.

8.3.4. TEST SETUP



- For the actual test configuration, please refer to the related item – Photographs of the Test Configuration.

NOTE:

TABLE-TOP EQUIPMENT

The configuration consisted of a wooden table 0.8 meters high standing on the **Ground Reference Plane**. The **GRP** consisted of a sheet of aluminum at least 0.25mm thick, and 2.5 meters square connected to the protective grounding system. A **Horizontal Coupling Plane** (1.6m x 0.8m) was placed on the table and attached to the **GRP** by means of a cable with 940k Ω total impedance. The equipment under test, was installed in a representative system as described in section 7 of IEC 61000-4-2, and its cables were placed on the **HCP** and isolated by an insulating support of 0.5mm thickness. A distance of 1-meter minimum was provided between the EUT and the walls of the laboratory and any other metallic structure.

FLOOR-STANDING EQUIPMENT

The equipment under test was installed in a representative system as described in section 7 of IEC 61000-4-2, and its cables were isolated from the Ground Reference Plane by an insulating support of 0.1-meter thickness. The GRP consisted of a sheet of aluminum that is at least 0.25mm thick, and 2.5 meters square connected to the protective grounding system and extended at least 0.5 meters from the EUT on all sides.

**8.3.5. TEST RESULTS**

Temperature	25°C	Humidity	48% RH
Pressure	998mbar	Tested by	Louis Shen
Required Passing Performance		Criterion B	

Air Discharge												
Test Points	Test Levels									Results		
	± 2 kV	Performance Criterion of testing		± 4 kV	Performance Criterion of testing		± 8 kV	Performance Criterion of testing		Pass	Fail	Observation
Front	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/> A	<input type="checkbox"/> B	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/> A	<input type="checkbox"/> B	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/> A	<input type="checkbox"/> B	<input checked="" type="checkbox"/>	<input type="checkbox"/>	Note 1
Back	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/> A	<input type="checkbox"/> B	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/> A	<input type="checkbox"/> B	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/> A	<input type="checkbox"/> B	<input checked="" type="checkbox"/>	<input type="checkbox"/>	Note 1
Left	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/> A	<input type="checkbox"/> B	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/> A	<input type="checkbox"/> B	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/> A	<input type="checkbox"/> B	<input checked="" type="checkbox"/>	<input type="checkbox"/>	Note 1
Right	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/> A	<input type="checkbox"/> B	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/> A	<input type="checkbox"/> B	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/> A	<input type="checkbox"/> B	<input checked="" type="checkbox"/>	<input type="checkbox"/>	Note 1
Top	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/> A	<input type="checkbox"/> B	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/> A	<input type="checkbox"/> B	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/> A	<input type="checkbox"/> B	<input checked="" type="checkbox"/>	<input type="checkbox"/>	Note 1
Bottom	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/> A	<input type="checkbox"/> B	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/> A	<input type="checkbox"/> B	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/> A	<input type="checkbox"/> B	<input checked="" type="checkbox"/>	<input type="checkbox"/>	Note 1

Contact Discharge												
Test Points	Test Levels									Results		
	± 2 kV	Performance Criterion of testing		± 4 kV	Performance Criterion of testing		± 8 kV	Performance Criterion of testing		Pass	Fail	Observation
Front	<input type="checkbox"/>	<input type="checkbox"/> A	<input type="checkbox"/> B	<input type="checkbox"/>	<input type="checkbox"/> A	<input type="checkbox"/> B	<input type="checkbox"/>	<input type="checkbox"/> A	<input type="checkbox"/> B	<input type="checkbox"/>	<input type="checkbox"/>	
Back	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/> A	<input type="checkbox"/> B	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/> A	<input type="checkbox"/> B	<input type="checkbox"/>	<input type="checkbox"/> A	<input type="checkbox"/> B	<input checked="" type="checkbox"/>	<input type="checkbox"/>	Note 1
Left	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/> A	<input type="checkbox"/> B	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/> A	<input type="checkbox"/> B	<input type="checkbox"/>	<input type="checkbox"/> A	<input type="checkbox"/> B	<input checked="" type="checkbox"/>	<input type="checkbox"/>	Note 1
Right	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/> A	<input type="checkbox"/> B	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/> A	<input type="checkbox"/> B	<input type="checkbox"/>	<input type="checkbox"/> A	<input type="checkbox"/> B	<input checked="" type="checkbox"/>	<input type="checkbox"/>	Note 1
Top	<input type="checkbox"/>	<input type="checkbox"/> A	<input type="checkbox"/> B	<input type="checkbox"/>	<input type="checkbox"/> A	<input type="checkbox"/> B	<input type="checkbox"/>	<input type="checkbox"/> A	<input type="checkbox"/> B	<input type="checkbox"/>	<input type="checkbox"/>	
Bottom	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/> A	<input type="checkbox"/> B	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/> A	<input type="checkbox"/> B	<input type="checkbox"/>	<input type="checkbox"/> A	<input type="checkbox"/> B	<input checked="" type="checkbox"/>	<input type="checkbox"/>	Note 1

For the tested points to EUT, please refer to attached page.

(Red arrow mark for Air Discharge and No any Contact Discharge events occurred on the test.)

Discharge To Horizontal Coupling Plane							
Side of EUT	Test Levels			Results			
	± 2 kV	± 4 kV	± 8 kV	Pass	Fail	Performance Criterion of testing	Observation
Front	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/> A <input type="checkbox"/> B	Note 1
Back	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/> A <input type="checkbox"/> B	Note 1
Left	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/> A <input type="checkbox"/> B	Note 1
Right	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/> A <input type="checkbox"/> B	Note 1

Discharge To Vertical Coupling Plane							
Side of EUT	Test Levels			Results			
	± 2 kV	± 4 kV	± 8 kV	Pass	Fail	Performance Criterion of testing	Observation
Front	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/> A <input type="checkbox"/> B	Note 1
Back	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/> A <input type="checkbox"/> B	Note 1
Left	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/> A <input type="checkbox"/> B	Note 1
Right	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/> A <input type="checkbox"/> B	Note 1

NOTE: 1. There was no change compared with initial operation during the test.

The Tested Points of EUT***Photo 1 of 6******Photo 2 of 6***

Photo 3 of 6**Photo 4 of 6**

Photo 5 of 6





Photo 6 of 6



**8.4. RADIATED, RADIO-FREQUENCY, ELECTROMAGNETIC FIELD (RS)****8.4.1. TEST SPECIFICATION****Basic Standard:** IEC 61000-4-3**Frequency Range:** For EN 55024: 80 MHz ~1000 MHz,
For EN 61000-6-1: 80 MHz ~1000 MHz, 1400 MHz ~2000 MHz,
2000 MHz ~2700 MHz**Field Strength:** EN 55024: 3 V/m
EN 61000-6-1: 3 V/m, 1 V/m**Modulation:** 1kHz Sine Wave, 80%, AM Modulation**Frequency Step:** 1 % of preceding frequency value**Polarity of Antenna:** Horizontal and Vertical**Test Distance:** 3 m**Antenna Height:** 1.5m**8.4.2. TEST INSTRUMENT**

733 RS Chamber				
Name of Equipment	Manufacturer	Model	Serial Number	Calibration Due
S.G.	Agilent	8648C	4108A05772	11/18/2010
Power Meter	R&S	NRVD	837794/029	08/11/2010
Power Sensor	R&S	URV5-Z2	835640/015	08/11/2010
Power Sensor	R&S	URV5-Z2	835640/016	08/11/2010
Power Amplifier	ar	150W1000	300300	N.C.R
Power Amplifier	ar	60S1G3M3	0328274	N.C.R
Bilog Antenna	SCHAFFNER	CBL 6140A	1221	N.C.R
Horn Antenna	EMCO	3115	00022257	11/10/2010
EM PROBE	ar	FL7006	0330722	03/15/2011
Test S/W	SW1006 (V1.13)			

NOTE: 1. The calibration interval of the above test instruments is 12 months and the calibrations are traceable to NML/ROC and NIST/USA.


2. N.C.R.= No Calibration required

8.4.3. TEST PROCEDURE (please refer to measurement standard or CCS SOP PA-023)

The test procedure was in accordance with IEC 61000-4-3

- a) The testing was performed in a fully anechoic chamber. The transmit antenna was located at a distance of 3 meters from the EUT.
- b) The frequency range is swept from 80 MHz to 1000 MHz, with the signal 80% amplitude modulated with a 1kHz sine-wave. The rate of sweep did not exceed 1.5×10^{-3} decade/s, where the frequency range is swept incrementally, the step size was 1% of preceding frequency value.
- c) The dwell time at each frequency shall be not less than the time necessary for the EUT to be able to respond.
- e) The test was performed with the EUT exposed to both vertically and horizontally polarized fields on each of the four sides.

8.4.4. TEST SETUP



- For the actual test configuration, please refer to the related item – Photographs of the Test Configuration.

NOTE:

TABLETOP EQUIPMENT

The EUT installed in a representative system as described in section 7 of IEC 61000-4-3 was placed on a non-conductive table 0.8 meters in height. The system under test was connected to the power and signal wire according to relevant installation instructions.

FLOOR STANDING EQUIPMENT

The EUT installed in a representative system as described in section 7 of IEC 61000-4-3 was placed on a non-conductive wood support 0.1 meters in height. The system under test was connected to the power and signal wire according to relevant installation instructions.

8.4.5. TEST RESULTS

Temperature	22°C	Humidity	47% RH
Pressure	999mbar	Dwell Time	3 sec.
Tested By	Louis Shen	Required Performance	Passing Criterion A

For EN 55024:

Frequency (MHz)	Polarity	Azimuth	Field Strength (V/m)	Performance Criterion of testing	Observation	Result
80 ~ 1000	V&H	0	3	<input checked="" type="checkbox"/> A <input type="checkbox"/> B	Note 1	PASS
80 ~ 1000	V&H	90	3	<input checked="" type="checkbox"/> A <input type="checkbox"/> B	Note 1	PASS
80 ~ 1000	V&H	180	3	<input checked="" type="checkbox"/> A <input type="checkbox"/> B	Note 1	PASS
80 ~ 1000	V&H	270	3	<input checked="" type="checkbox"/> A <input type="checkbox"/> B	Note 1	PASS

For EN 61000-6-1:

Frequency (MHz)	Polarity	Azimuth	Field Strength (V/m)	Performance Criterion of testing	Observation	Result
80 ~ 1000	V&H	0	3	<input checked="" type="checkbox"/> A <input type="checkbox"/> B	Note 1	PASS
80 ~ 1000	V&H	90	3	<input checked="" type="checkbox"/> A <input type="checkbox"/> B	Note 1	PASS
80 ~ 1000	V&H	180	3	<input checked="" type="checkbox"/> A <input type="checkbox"/> B	Note 1	PASS
80 ~ 1000	V&H	270	3	<input checked="" type="checkbox"/> A <input type="checkbox"/> B	Note 1	PASS
1400 ~ 2000	V&H	0	3	<input checked="" type="checkbox"/> A <input type="checkbox"/> B	Note 1	PASS
1400 ~ 2000	V&H	90	3	<input checked="" type="checkbox"/> A <input type="checkbox"/> B	Note 1	PASS
1400 ~ 2000	V&H	180	3	<input checked="" type="checkbox"/> A <input type="checkbox"/> B	Note 1	PASS
1400 ~ 2000	V&H	270	3	<input checked="" type="checkbox"/> A <input type="checkbox"/> B	Note 1	PASS
2000 ~ 2700	V&H	0	1	<input checked="" type="checkbox"/> A <input type="checkbox"/> B	Note 1	PASS
2000 ~ 2700	V&H	90	1	<input checked="" type="checkbox"/> A <input type="checkbox"/> B	Note 1	PASS
2000 ~ 2700	V&H	180	1	<input checked="" type="checkbox"/> A <input type="checkbox"/> B	Note 1	PASS
2000 ~ 2700	V&H	270	1	<input checked="" type="checkbox"/> A <input type="checkbox"/> B	Note 1	PASS

NOTE: 1. There was no change compared with the initial operation during the test.



8.5. ELECTRICAL FAST TRANSIENT (EFT)

8.5.1. TEST SPECIFICATION

Basic Standard: IEC 61000-4-4

Test Voltage: AC Power Port: 1kV
DC Power Port: 0.5kV
Signal Ports and Telecommunication Ports: 0.5kV

Polarity: Positive & Negative

Impulse Frequency: 5 kHz

Impulse Wave-shape: 5/50 ns

Burst Duration: 15 ms

Burst Period: 3 Hz

Test Duration: Not less than 1 min.

8.5.2. TEST INSTRUMENT


Immunity Shield Room				
Name of Equipment	Manufacturer	Model	Serial Number	Calibration Due
EMC TEST SYSTEM	EMC-PARTNER	TRANSIENT-2000	754	09/01/2010
Clamp	HAEFELY TRENCH	093 506.1	080 421.13	N.C.R
Test S/W	Genecs (2.54)			

NOTE: 1. The calibration interval of the above test instruments is 12 months and the calibrations are traceable to NML/ROC and NIST/USA.
2. N.C.R.= No Calibration required

8.5.3. TEST PROCEDURE (please refer to measurement standard or CCS SOP PA-024)

- Both positive and negative polarity discharges were applied.
- The length of the "hot wire" from the coaxial output of the EFT generator to the terminals on the EUT should not exceed 1 meter.
- The duration time of each test sequential was 1 minute.
- The transient/burst waveform was in accordance with IEC 61000-4-4, 5/50ns.

8.5.4. TEST SETUP



- For the actual test configuration, please refer to the related item – Photographs of the Test Configuration.

NOTE:

TABLETOP EQUIPMENT

The configuration consisted of a wooden table (0.8m high) standing on the Ground Reference Plane. The GRP consisted of a sheet of aluminum (at least 0.25mm thick and 2.5m square) connected to the protective grounding system. A minimum distance of 0.5m was provided between the EUT and the walls of the laboratory or any other metallic structure.

FLOOR STANDING EQUIPMENT

The EUT installed in a representative system as described in section 7 of IEC 61000-4-4 and its cables, were isolated from the Ground Reference Plane by an insulating support that is 0.1-meter thick. The GRP consisted of a sheet of aluminum (at least 0.25mm thick and 2.5m square) connected to the protective grounding system.

**8.5.5. TEST RESULTS**

Temperature	24°C	Humidity	48% RH
Pressure	999mbar	Tested by	Louis Shen
Required Passing Performance		Criterion B	

Test Point	Polarity	Test Level (kV)	Performance Criterion	Observation	Result
L	+/-	1	<input checked="" type="checkbox"/> A <input type="checkbox"/> B	Note 1	PASS
N	+/-	1	<input checked="" type="checkbox"/> A <input type="checkbox"/> B	Note 1	PASS
PE	+/-	1	<input checked="" type="checkbox"/> A <input type="checkbox"/> B	Note 1	PASS
L+N	+/-	1	<input checked="" type="checkbox"/> A <input type="checkbox"/> B	Note 1	PASS
L +PE	+/-	1	<input checked="" type="checkbox"/> A <input type="checkbox"/> B	Note 1	PASS
N + PE	+/-	1	<input checked="" type="checkbox"/> A <input type="checkbox"/> B	Note 1	PASS
L +N +PE	+/-	1	<input checked="" type="checkbox"/> A <input type="checkbox"/> B	Note 1	PASS
LAN	+/-	0.5	<input checked="" type="checkbox"/> A <input type="checkbox"/> B	Note 1	PASS

NOTE: 1. There was no change compared with the initial operation during the test.



8.6. SURGE IMMUNITY TEST

8.6.1. TEST SPECIFICATION

Basic Standard:	IEC 61000-4-5
Wave-Shape:	Combination Wave 1.2/50 us or 10/700 us Open Circuit Voltage 8/20 μ s or 5/320 Short Circuit Current
Test Voltage:	For EN 55024: AC Power Port ~ line to line: 1kV, line to earth (ground): 2kV DC Power Port ~ line to earth: 0.5kV Signal Ports and Telecommunication Ports ~ line to ground: 1kV For EN 61000-6-1: AC Power Port ~ line to line: 1kV, line to earth: 2kV DC Power Port ~ line to earth: 0.5kV, line to line: 0.5kV
Surge Input/Output:	Power Line: L1-L2 / L1-PE / L2-PE
Generator Source Impedance:	2 ohm between networks 12 ohm between network and ground
Polarity:	Positive/Negative
Phase Angle:	0 / 90 / 180 / 270
Pulse Repetition Rate:	1 time / min. (maximum)
Number of Tests:	5 positive and 5 negative at selected points

8.6.2. TEST INSTRUMENT

Immunity Shield Room				
Name of Equipment	Manufacturer	Model	Serial Number	Calibration Due
Surge Tester	HAEFELY TRENCH	PSUGER 4010	583 334-71	09/01/2010
Test S/W	Winpats (3.25)			

NOTE: The calibration interval of the above test instruments is 12 months and the calibrations are traceable to NML/ROC and NIST/USA.

8.6.3. TEST PROCEDURE (please refer to measurement standard or CCS SOP PA-025)

a) For EUT power supply:


The surge is applied to the EUT power supply terminals via the capacitive coupling network. Decoupling networks are required in order to avoid possible adverse effects on equipment not under test that may be powered by the same lines, and to provide sufficient decoupling impedance to the surge wave. The power cord between the EUT and the coupling/decoupling networks was shorter than 2 meters in length.

b) For test applied to unshielded un-symmetrically operated interconnection lines of EUT:

The surge was applied to the lines via the capacitive coupling. The coupling / decoupling networks didn't influence the specified functional conditions of the EUT. The interconnection line between the EUT and the coupling/decoupling networks was shorter than 2 meters in length.

c) For test applied to unshielded symmetrically operated interconnection / telecommunication lines of EUT:

The surge was applied to the lines via gas arrestors coupling. Test levels below the ignition point of the coupling arrestor were not specified. The interconnection line between the EUT and the coupling/decoupling networks was shorter than 2 meters in length.

8.6.4. TEST SETUP

- For the actual test configuration, please refer to the related item – Photographs of the Test Configuration.

**8.6.5. TEST RESULTS**

Temperature	23°C	Humidity	48% RH
Pressure	999mbar	Tested by	Louis Shen
Required Passing Performance		Criterion B	

Test Point	Polarity	Test Level (kV)	Performance Criterion	Observation	Result
L - N	+/-	1	<input checked="" type="checkbox"/> A <input type="checkbox"/> B	Note 1	PASS
L - PE	+/-	2	<input checked="" type="checkbox"/> A <input type="checkbox"/> B	Note 1	PASS
N - PE	+/-	2	<input checked="" type="checkbox"/> A <input type="checkbox"/> B	Note 1	PASS

NOTE: 1. There was no change compared with the initial operation during the test.



8.7. CONDUCTED RADIO FREQUENCY DISTURBANCES (CS)

8.7.1. TEST SPECIFICATION

Basic Standard:	IEC 61000-4-6
Frequency Range:	0.15 MHz ~ 80 MHz
Field Strength:	3 Vrms
Modulation:	1kHz Sine Wave, 80%, AM Modulation
Frequency Step:	1 % of preceding frequency value
Coupled cable:	Power Mains, Unshielded
Coupling device:	CDN-M3 (3 wires) CDN-T4 for LAN

8.7.2. TEST INSTRUMENT

Immunity Shield Room				
Name of Equipment	Manufacturer	Model	Serial Number	Calibration Due
S.G.	Agilent	8648C	4108A05772	11/18/2010
Power Meter	R&S	NRVD	837794/029	08/11/2010
Power Sensor	R&S	URV5-Z2	835640/015	08/11/2010
Power Sensor	R&S	URV5-Z2	835640/016	08/11/2010
Power Amplifier	ar	75A250AM1	306334	N.C.R
CDN	FCC	FCC-801-M3-16A	99122	11/30/2010
CDN	FCC	FCC-801-T4-RJ45	04008	11/30/2010
Test S/W	SW1006 (V1.13)			

NOTE: 1. The calibration interval of the above test instruments is 12 months and the calibrations are traceable to NML/ROC and NIST/USA.
2. N.C.R.= No Calibration required



8.7.3. TEST PROCEDURE (please refer to measurement standard or CCS SOP PA-026)

The EUT shall be tested within its intended operating and climatic conditions.


The test shall be performed with the test generator connected to each of the coupling and decoupling devices in turn, while the other non-excited RF input ports of the coupling devices are terminated by a 50-ohm load resistor.

The frequency range was swept from 150 kHz to 80 MHz, using the signal level established during the setting process and with a disturbance signal of 80 % amplitude. The signal was modulated with a 1 kHz sine wave, pausing to adjust the RF signal level or the switch coupling devices as necessary. The sweep rate was 1.5×10^{-3} decades/s. Where the frequency range is swept incrementally, the step size was 1 % of preceding frequency value from 150 kHz to 80 MHz.

The dwell time at each frequency was less than the time necessary for the EUT to be exercised, and able to respond. Sensitive frequencies such as clock frequency(ies) and harmonics or frequencies of dominant interest, was analyzed separately.

Attempts were made to fully exercise the EUT during testing, and to fully interrogate all exercise modes selected for susceptibility.

8.7.4. TEST SETUP



Note: 1. The EUT is setup 0.1m above Ground Reference Plane

2. The CDNs and / or EM clamp used for real test depends on ports and cables configuration of EUT.

- For the actual test configuration, please refer to the related item – Photographs of the Test Configuration.

NOTE:

TABLE-TOP AND FLOOR-STANDING EQUIPMENT

The equipment to be tested was placed on an insulating support of 0.1 meters height above a ground reference plane. All relevant cables shall be provided with the appropriate coupling and decoupling devices at a distance between 0.1 meters and 0.3 meters from the projected geometry of the EUT on the ground reference plane.

8.7.5. TEST RESULTS

Temperature	24°C	Humidity	48% RH
Pressure	1001mbar	Tested by	Louis Shen
Required Passing Performance		Criterion A	

Frequency Band (MHz)	Field Strength (Vrms)	Cable	Injection Method	Performance Criterion of testing	Observation	Result
0.15 ~ 80	3	Power Line	CDN-M3	<input checked="" type="checkbox"/> A <input type="checkbox"/> B	Note 1	PASS
0.15 ~ 80	3	LAN	CDN-T4	<input checked="" type="checkbox"/> A <input type="checkbox"/> B	Note 1	PASS

NOTE: 1. There was no change compared with initial operation during the test.



8.8. POWER FREQUENCY MAGNETIC FIELD

8.8.1. TEST SPECIFICATION

Basic Standard:	IEC 61000-4-8
Frequency Range:	50Hz, 60Hz
Field Strength:	EN 55024: 1 A/m EN 61000-6-1: 3 A/m
Observation Time:	1 minute
Inductance Coil:	Rectangular type, 1mx1m

8.8.2. TEST INSTRUMENT


Immunity Shield Room				
Name of Equipment	Manufacturer	Model	Serial Number	Calibration Due
TRIAX ELF Magnetic Field Meter	F.W.BELL	4090	9711	11/26/2010
Clamp Meter	National	300K	11-5980 K	11/25/2010
Magnetic Field Tester	HAEFELY TRENCH	MAG 100.1	080 938-01	06/04/2011

NOTE: 1. The calibration interval of the above test instruments is 12 months and the calibrations are traceable to NML/ROC and NIST/USA.
2. N.C.R.= No Calibration required

8.8.3. TEST PROCEDURE (please refer to measurement standard or CCS SOP PA-027)

- The equipment was configured and connected to satisfy its functional requirements. It shall be placed on the GRP with the interposition of a 0.1m-thick insulating support.
- The equipment cabinets shall be connected to the safety earth directly on the GRP via the earth terminal of the EUT.
- The power supply, input and output circuits shall be connected to the sources of power supply, control and signal.
- The cables supplied or recommended by the equipment manufacturer shall be used. 1 meter of all cables used shall be exposed to the magnetic field.

8.8.4. TEST SETUP



- For the actual test configuration, please refer to the related item – Photographs of the Test Configuration.

NOTE:

TABLETOP EQUIPMENT

The equipment shall be subjected to the test magnetic field by using the induction coil of standard dimension (1 m x 1 m). The induction coil shall then be rotated by 90 degrees in order to expose the EUT to the test field with different orientations.

FLOOR-STANDING EQUIPMENT

The equipment shall be subjected to the test magnetic field by using induction coils of suitable dimensions. The test shall be repeated by moving and shifting the induction coils, in order to test the whole volume of the EUT for each orthogonal direction. The test shall be repeated with the coil shifted to different positions along the side of the EUT, in steps corresponding to 50 % of the shortest side of the coil. The induction coil shall then be rotated by 90 degrees in order to expose the EUT to the test field with different orientations.

**8.8.5. TEST RESULTS**

Temperature	24°C	Humidity	47% RH
Pressure	997mbar	Tested by	Louis Shen
Required Passing Performance	Criterion A		

For EN 55024:

DIRECTION	Field Strength (A/m)	Performance Criterion of testing	OBSERVATION	RESULTS
X	1	<input checked="" type="checkbox"/> A <input type="checkbox"/> B	Note 1	Pass
Y	1	<input checked="" type="checkbox"/> A <input type="checkbox"/> B	Note 1	Pass
Z	1	<input checked="" type="checkbox"/> A <input type="checkbox"/> B	Note 1	Pass

For EN 61000-6-1:

DIRECTION	Field Strength (A/m)	Performance Criterion of testing	OBSERVATION	RESULTS
X	3	<input checked="" type="checkbox"/> A <input type="checkbox"/> B	Note 1	Pass
Y	3	<input checked="" type="checkbox"/> A <input type="checkbox"/> B	Note 1	Pass
Z	3	<input checked="" type="checkbox"/> A <input type="checkbox"/> B	Note 1	Pass

NOTE: 1. There was no change compared with the initial operation during the test.



8.9. VOLTAGE DIP & VOLTAGE INTERRUPTIONS

8.9.1. TEST SPECIFICATION

Basic Standard: IEC 61000-4-11

Test duration time: Minimum three test events in sequence

Interval between event: Minimum 10 seconds

Angle: 0~360 degree

Step: 45 degree


8.9.2. TEST INSTRUMENT

Immunity shielded room				
Name of Equipment	Manufacturer	Model	Serial Number	Calibration Due
Dips/Interruption and Variations Simulator	HAEFELY TRENCH	PLINE 1610	080 344-05	04/29/2010
Test S/W	Winpats (3.25)			

NOTE: The calibration interval of the above test instruments is 12 months and the calibrations are traceable to NML/ROC and NIST/USA.

8.9.3. TEST PROCEDURE (please refer to measurement standard or CCS SOP PA-028)

1. The EUT and support units were located on a wooden table, 0.8 m away from ground floor.
2. Setting the parameter of tests and then perform the test software of test simulator.
3. Conditions changes to occur at 0 degree crossover point of the voltage waveform.
4. Recording the test result in test record form.
5. Removes the Battery Pack to test if any.

8.9.4. TEST SETUP

- For the actual test configuration, please refer to the related item – Photographs of the Test Configuration.

8.9.5. TEST RESULTS

Temperature	23°C	Humidity	46% RH
Pressure	998mbar	Tested by	Louis Shen
Required Passing Performance	EN 55024: Criterion B: >95% reduction 0.5 period Criterion C: 30% reduction 25 period & >95% reduction 250 period EN 61000-6-1: Criterion B: 30% reduction 0.5 period Criterion C: 60% reduction 5 period & >95% reduction 250 period		

EN 55024:

Test Power: 230Vac, 50Hz				
Voltage (% Reduction)	Duration (Period)	Performance Criterion	Observation	Test Result
>95	0.5	<input checked="" type="checkbox"/> A <input type="checkbox"/> B <input type="checkbox"/> C	Note 1	PASS
30	25	<input checked="" type="checkbox"/> A <input type="checkbox"/> B <input type="checkbox"/> C	Note 1	PASS
>95	250	<input type="checkbox"/> A <input type="checkbox"/> B <input checked="" type="checkbox"/> C	Note 2	PASS

EN 61000-6-1:

Test Power: 230Vac, 50Hz				
Voltage (% Reduction)	Duration (Period)	Performance Criterion	Observation	Test Result
30	0.5	<input checked="" type="checkbox"/> A <input type="checkbox"/> B <input type="checkbox"/> C	Note 1	PASS
60	5	<input checked="" type="checkbox"/> A <input type="checkbox"/> B <input type="checkbox"/> C	Note 1	PASS
>95	250	<input type="checkbox"/> A <input type="checkbox"/> B <input checked="" type="checkbox"/> C	Note 2	PASS

NOTE: 1. There was no change compared with initial operation during and after the test. No unintentional response was found during the test.
 2. The function stopped during the test, but can be recoverable manually after the test.

9 PHOTOGRAPHS OF THE TEST CONFIGURATION

CONDUCTED EMISSION TEST



CONDUCTED EMISSION TEST AT TELECOMMUNICATION PORTS

RJ45 Telecom Port with ISN (10/100 Mbps)



RADIATED EMISSION TEST



POWER HARMONIC & VOLTAGE FLUCTUATION / FLICKER TEST



ELECTROSTATIC DISCHARGE TEST




RADIATED ELECTROMAGNETIC FIELD TEST



FAST TRANSIENTS/BURST TEST (POWER LINE)




FAST TRANSIENTS/BURST TEST (TELECOMMUNICATION PORT)



SURGE IMMUNITY TEST (POWER LINE)



CONDUCTED DISTURBANCE, INDUCED BY RADIO-FREQUENCY FIELDS TEST (POWER LINE)**CONDUCTED DISTURBANCE, INDUCED BY RADIO-FREQUENCY FIELDS TEST (LAN)**

POWER FREQUENCY MAGNETIC FIELD IMMUNITY TEST



VOLTAGE DIPS / INTERRUPTION TEST



PHOTOGRAPHS OF EUT







Power Adapter



