

Statement of Conformity

Best Laboratory Co., Ltd.

No. 336, Ba Lian RD., Sec. 1, Hsi Chih City, Taipei Hsien, Taiwan, R.O.C.
Telephone: 886-2-2646-2899 Facsimile: 886-2-2646-2870

EMC Certificate

Applicant : Advantech Co., Ltd.
Address : Fl.4, No. 108-3, Ming-Chuan Road,
Shing-Tien City, Taipei, Taiwan, R.O.C.
Equipment : Industrial PC
Model : PCA-6004


Has fully complied with the requirements set out in the council directive on the approximation of the law of the members states relating to Electromagnetic Compatibility Directive (89/336/EEC). For the evaluation regarding EMC, the following standards were applied:

EMI: EN 50081-1:1993 -> EN 55022:1999, EN 61000-3-2:2000, EN 61000-3-3:1995

EMS: EN 55024:1998 -> EN 61000-4-2:1998, EN 61000-4-3:1998,
EN 61000-4-4:1995, EN 61000-4-5:1995,
EN 61000-4-6:1996, EN 61000-4-8:1993,

The date of the measurement: Mar. 21, 2002
The date of the certification signed: Mar. 23, 2002
The number of EMC Certificate: CER-A01-CE-648

Test Laboratory



Quality Department Manager: JEFF CHIU



This verification is based on a single evaluation of one sample of above-mentioned products. It does not imply any assessment of the whole production and does not permit the use of the logo of the test laboratory.

EMC TEST REPORT

Applicant : Advantech Co., Ltd.
Equipment : Industrial PC
Model : PCA-6004

Test Report Certification

Best Laboratory Co., Ltd.

No. 336, Ba Lian Rd., Sec. 1, Hsi Chih City, Taipei Hsien, Taiwan, R.O.C.
Tel: 886-2-2646-2899 Fax: 886-2-2646-2870

Applicant : Advantech Co., Ltd.
Address : Fl.4, No. 108-3, Ming-Chuan Road,
Shing-Tien City, Taipei, Taiwan, R.O.C.
Equipment : Industrial PC
Model : PCA-6004
Device's Class : Class A Device
Measurement Standard : EN 50081-1/1992, EN 55024/1998
Measurement Procedure : EN 55022/1998, EN 61000-3-2/2000, EN 61000-3-3/1995
EN 61000-4-2/1998, EN 61000-4-3/1998, EN 61000-4-4/1995,
EN 61000-4-5/1995, EN 61000-4-6/1996, EN 61000-4-8/1993
EN 61000-4-11/1994
Operating Voltage : 230VAC, 50Hz
Test Result : **Compliance** (Detail showed in the test report)
Sample Received : Mar. 12, 2002
Test Date : Mar. 21, 2002
Report Number : RE-A01-CE-648
Test Firm : No. 336, Ba Lian Rd., Sec. 1,
Hsi Chih City, Taipei Hsien, Taiwan, R.O.C.

Remark:

- (1) The test report is only relating to the sample tested
- (2) The test report shall not be reproduced except in full, without the written approval of Best Laboratory Co., Ltd.
- (3) The test result of this report are traceable to the national or international standards.

Prepared : Ivan Hsieh
IVAN HSIEH

Approved : Jeff Chiu (Title: Quality Department Manager)
JEFF CHIU

Date Issued : Mar. 23, 2002

Contain

1	General Information	
1.1	EUT Description.....	4
1.2	Test System Detail.....	5
1.3	Tested Configuration.....	8
1.4	EUT Exercise Software.....	9
1.5	Test Performed.....	9
2	Conducted Emission Measurement	
2.1	Test Equipment List.....	10
2.2	Test Set-Up.....	10
2.3	Limit	10
2.4	Test Procedure.....	11
2.5	Test Specification.....	11
2.6	Test Result.....	11
3	Radiated Emission Measurement	
3.1	Test Equipment List.....	12
3.2	Test Set-Up.....	12
3.3	Limit.....	13
3.4	Test Procedure.....	13
3.5	Test Specification.....	13
3.6	Test Result.....	13
4	Power Harmonic and Voltage Fluctuation	
4.1	Power Harmonic and voltage Fluctuation test Equipment List.....	14
4.2	Test Set-Up.....	14
4.3	Limit.....	14
4.4	Test Procedure.....	15
4.5	Test Specification.....	15
4.6	Test Result.....	15
5	Electrostatic Discharge (ESD)	
5.1	Test Equipment List.....	16
5.2	Test Set-Up.....	16
5.3	Test Level.....	16
5.4	Test Procedure.....	17
5.5	Test Specification.....	17
5.6	Test Result.....	17
6	Radiated Susceptibility (RS)	
6.1	Test Equipment List.....	18
6.2	Test Set-Up.....	18
6.3	Test Level.....	18
6.4	Test Procedure.....	19
6.5	Test Specification.....	19
6.6	Test Result.....	19

7 Electrical Fast Transient/Burst

7.1 Test Equipment List.....	20
7.2 Test Set-Up.....	20
7.3 Test Level.....	20
7.4 Test Procedure.....	21
7.5 Test Specification.....	21
7.6 Test Result.....	21

8 Surge

8.1 Test Equipment List.....	22
8.2 Test Set-Up.....	22
8.3 Test Level.....	22
8.4 Test Procedure.....	23
8.5 Test Specification.....	23
8.6 Test Result.....	23

9 Conducted Susceptibility

9.1 Test Equipment List.....	24
9.2 Test Set-Up.....	24
9.3 Test Level.....	25
9.4 Test Procedure.....	25
9.5 Test Specification.....	25
9.6 Test Result.....	25

10 Power Frequency Magnetic Field

10.1 Test Equipment List.....	26
10.2 Test Set-Up.....	26
10.3 Test Level.....	26
10.4 Test Procedure.....	27
10.5 Test Specification.....	27
10.6 Test Result.....	27

11 Voltage DIPS and Interruption Measurement

11.1 Test Equipment List.....	28
11.2 Test Set-Up.....	28
11.3 Test Level.....	28
11.4 Test Procedure.....	29
11.5 Test Specification.....	29
11.6 Test Result.....	29

12 Modification List**13 Appendix**

Appendix A: Summary of Test Result.....	32
Appendix B: The Photograph of measurement.....	49
Appendix C: The Detail Photograph of EUT.....	56

1. General Information

1.1 EUT Description

Applicant	: Advantech Co., Ltd.
Address	: Fl.4, No. 108-3, Ming-Chuan Road, Shing-Tien City, Taipei, Taiwan, R.O.C.
Equipment	: Industrial PC
Model	: PCA-6004
Device's Class	: Class A Device
Operation Voltage	: 230VAC, 50Hz
Output Ports	:
Monitor Port	: Connected with one monitor which data cable is 1.8 meters long, shielded, with ferrite core.
USB Ports	: The two USB ports are each connected with one USB mouse which data cable is 120 cm long, shielded, no ferrite bead.
Serial#1 Port	: Connected with one external modem, via one RS-232 cable which data cable is 1.8 meters long, non-shielded, no ferrite bead.
Serial#2 Port	: Connected with a 1.8 meters long, non-shielded, no ferrite bead, RS-232 cable which is left non-terminal.
Parallel Port	: Connected with one printer with data cable is 1.8 meters long, shielded, no ferrite bead.
LAN Port	: Via one RJ-45 cable, 30 meters long, non-shielded, no ferrite bead, to the far-end HUB.
PS/2 Port	: Connected with one PS/2 keyboard and PS/2 mouse which length is 120 cm long, non-shielded, no ferrite bead, via a Y data cable which length is 30 cm long, non-shielded, no ferrite bead.
Power Port	: Via a 180 cm long, non-shielded, with ferrite bead, power cable to the AC power source.

1.2 Test System Detail

Monitor : HITACHI

Model No. : CM771U
Serial No. : V0E001074
FCC ID : DoC Approval
BSMI : 3882A707
Power Type : 100-240VAC, 50/60Hz, 1.5A, Switching
Power Cord : 180cm long, non-shielded, no ferrite bead.
Data Cable : 120cm long, shielded, with ferrite bead
Backshell : Metal
Connected Port : VGA Port

Keyboard : Logitech

Model No. : SK-720
Serial No. : N/A
FCC ID : GYUR49SK
BSMI : 3872A806
Power Type : By PC
Data Cable : 180cm long, shielded, no ferrite bead
Backshell : Metal
Connected Port : PS/2 Keyboard Port

Mouse : Logitech

Model No. : M-S48a
Serial No. : N/A
FCC ID : JNZ201213
BSMI : 4882A001
Power Type : By PC
Data Cable : 120cm long, non-shielded, no ferrite bead
Backshell : Metal
Connected Port : PS/2 Mouse Port

Modem : ACEEX

Model No. : XDM-9624
Serial No. : 0017884
FCC ID : IFAXDM-9624
Power Type : 230VAC, 50Hz / 9VAC, 1A
Power Core : 1.9meters long, non-shielded, no ferrite bead
Data Cable : RS-232, shielded, 1.2meters long, no ferrite bead
RJ11C x 2, 7' long, non-shielded, no ferrite bead
Backshell : Metal
Connected Port : Serial Port.

Printer : Epson

Model No. : P950
 Serial No. : BW9Y113923
 FCC ID : DoC Approval
 BSMI : 3872P001
 Power Type : 230VAC, 50Hz, 0.4A
 Power Core : 165cm long, non-shielded, no ferrite bead
 Data Cable : 120cm long, shielded, no ferrite bead
 Backshell : Metal
 Connected Port : Parallel Port

USB Mouse : Logitech

Model No. : M-BB48
 Serial No. : LZE92250126
 FCC ID : DoC Approval
 BSMI : 4872A221
 Power Type : By PC
 Data Cable : 120cm long, shielded, no ferrite bead
 Backshell : Metal
 Connected Port : USB Port

Case : Advantech

Model No. : IPC-610
 Power Cord : 180cm long, non-shielded, no ferrite bead.

CPU : VIA

Model No. : Cyrix III 800AMHz

RAM : NEC

Model No. : UG516T6646JK-PL 128MB
 Serial No. : 0138-MO09200006

CPU Board : Advantech

Model No. : PCA-6004
 Serial No. : 1906600401

Back Plane : Advantech

Model No. : PCA-6114P4
 Serial No. : 96383393

Hard disk driver : Seagate

Model No. : ST320414A
 Serial No. : 7EC02YQV
 FCC ID : DoC Approval
 BSMI : 3892C924
 Power Type : 115/230VAC, 60/50Hz, 12VDC, 500mA
 Power Cord : 26cm long, non-shielded, no ferrite bead.

Floppy disk driver : Teac

Model No. : FD-235HF
Serial No. : L485713
FCC ID : DoC Approval
Power Type : 115/230VAC, 60/50Hz, 7/4A, Switching
Power Cord : 26cm long, non-shielded, no ferrite bead.

CD-ROM : Asus

Model No. : CD-S400/A
Serial No. : 94148AB0271580
FCC ID : DoC Approval
Power Type : 115/230VAC, 60/50Hz, 0.9/1.5A, Switching
Power Cord : 30cm long, non-shielded, no ferrite bead.

Power : Seasonic


Model No. : SSH-250G
Serial No. : C03024251
FCC ID : DoC Approval
Power Type : 100/240VAC, 60/50Hz, 6/4A, Switching
Power Cord : 40cm long, non-shielded, no ferrite bead.

1.3 EUT Configuration

- (1) The PS/2 port of EUT is connected with one PS/2 keyboard and PS/2 mouse, via a Y data cable.
- (2) The serial#1 port of EUT is connected with an external modem.
- (3) The serial#2 ports of EUT is connected with a RS-232 cable.
- (4) The monitor port of EUT is connected with one monitor.
- (5) The LAN port of EUT is connected with the HUB located in far-end.
- (6) The parallel port of EUT is connected with one printer.
- (7) The two USB ports of EUT are each connected with one USB mouse.
- (8) The power port of EUT is connected with the AC power source via one power cable.

(***PS: Please refers to the Photograph***)

Drawing of Configuration



1.4 EUT Exercise Software

The testing software is provided by the applicant.

It is designed to exercise the EUT in a manner similar to a typical use. The software will send an " H " pattern to the monitor and the " H " pattern will be shown on the monitor. The software will also send an " H " pattern to the printer and the " H " pattern will be printed out at the printer. The software will also send the data to the modem and the modem will respond to the EUT. The HDD will continuously working sequence in the " Write-Read-Delete " mode. At the same time, the mouse and keyboard will be in continuously self-test mode and responded to the EUT. The software will enable all functions of EUT.

1.5 Test Performed

Conducted emissions were investigated over the frequency range from 0.15MHz to 30MHz using a receiver which bandwidth is set at 9KHz.

Radiated emissions were investigated over the frequency range from 30MHz to 1000MHz using a receiver which bandwidth is set at 120KHz. Radiated measurement was performed at distance that from an antenna to EUT is 10 meters.

The testing result of pretest was shown out that the "Transmitting/Receiving" mode is worse than the " Standby " mode. So, the final measurement was made on the "Transmitting/Receiving" mode.

There are three video resolution testing modes when the tests and the measurements were performed: "640 X 480 MHz", "1024 X 768 MHz", "1600 X 1200 MHz".

Because of the specification of the LAN port of EUT, there are two testing modes when the measurements were taken: 10MHz and 100MHz.


2 Conducted Emission Measurement

2.1 Test Equipment

No.	Instrument	Manufacture	Model	Serial No.	Last Calibrate
1.	LISN (EUT)	Rolf Heine	NNB-2/16Z	99084	May 14, 2001
2.	LISN (AXE)	Rolf Heine	NNB-2/16Z	99086	May 14, 2001
3.	EMI Receiver	Rohde & Schwarz	ESI 7	830154/001	June 27, 2001
4.	50 Ω Terminator	Amphenol	46650-51	N/A	Dec. 10, 2001
5.	RF Cable	Belden	M17/158	MIL-C-17	Jan. 20, 2002

Remark: All equipment upon which need to calibrated are with calibration period of one year.

2.2 Test Set-Up



2.3 Limit

Frequency	Limit (dB μ V)			
	Class A		Class B	
MHz	Quasi Peak	Average	Quasi Peak	Average
0.15 ~ 0.50	79	66	66 ~ 56	56 ~ 46
0.50 ~ 5.0	73	60	56	46
5.0 ~ 30.0	73	60	60	50

Remark: In the above table, the tighter limit applies at the band edges.

2.4 Test Procedure

The EUT and simulators are connected to the main power through a line impedance stabilization network (LISN). It provides a 50 ohm / 50 μ H coupling impedance for the measuring equipment. The peripheral devices are also connected to the main power through a LISN that provides a 50 ohm / 50 μ H coupling impedance with 50 ohm termination. (Please refers to the block diagram of the test setup and photograph.)

Both sides of AC line are checked for the maximum conducted emission interference. In order to find the maximum emissions, the relating positions of equipment and all of the interference cables must be changed according to EN 55022/1998 regulation: The measurement procedure on conducted emission interference.

The resolution bandwidth of the field strength meter (Rohde & Schwarz) is set at 9KHz.

2.5 Test Specification

According to the EN 55022/1998

2.6 Test Result

The emissions that come from the EUT were below the specified limits. The worst case of conducted emissions measurement are shown in the appendix A. The acceptance criterion was met and the EUT has pass the measurement.

2.7 Deviation from the Test Method

No Deviation.


3. Radiated Emission Measurement

3.1 Test Equipment List

No.	Instrument	Manufacture	Model	Serial No.	Last Calibrate
1.	Antenna	Mess-Elektronik	VULB 9160	9160-3078	Jan. 19, 2002
2.	EMI Receiver	Rohde & Schwarz	ESI 7	830154/001	June 22, 2001
3.	RF Cable	Adventest	AD-N-CA-01	2000-0220	Jan. 20, 2002
4.	OATS	Bestlab	N/A	OATS#1	May 28, 2001

Remark: All equipment upon which need to calibrated are with calibration period of one year.

3.2 Test Setup



3.3 Limit

Frequency MHz	Class A		Class B	
	Distance (Meter)	Limit (dB μ V)	Distance (Meter)	Limit (dB μ V)
30 ~ 230	10	40	10	30
230 ~ 1000	10	47	10	37

Remark: In the above table, the tighter limit applies at the band edges

3.4 Test Procedure

The EUT and its simulators are placed on turn table, non-ducted and wooden, which is 0.8 meter above ground. The turn table rotates 360 degree to determine the position of the maximum emission level. The EUT was positioned such that distance from antenna to the EUT is 10 meters.

The antenna is moved up and down between 1 meter to 4 meter to receive the maximum emission level.

Both horizontal and vertical polarization of the antenna are set on measurement. In order to find the maximum emission, all of the interference cables must be manipulated according to EN 55022/1998 regulation: the test procedure of the radiated emission measurement.

The bandwidth set on the field strength is 120KHz when the frequency range is below 1GHz

3.5 Test Specification

According to EN 55022/1998

3.6 Test Result

The emissions that come from the EUT was below the specified limits. The worst case of conducted emissions measurement are shown in the appendix A. The acceptance criterion was met and the EUT has pass the measurement.

3.7 Deviation from the Test Method

No Deviation.


4. Power Harmonic and Voltage Fluctuation Measurement

4.1 Power Harmonic and Voltage Fluctuation Test Equipment List

No.	Instrument	Manufacture	Model	Serial No.	Last Calibrate
1.	H/F Test System	EMC Partner	Harmonic-1000	325807	May. 10, 2001

Remark: All equipment upon which need to calibrated are with calibration period of 1 year.

4.2 Test Setup



4.3 Limit of Harmonic Current

Limit of Harmonic Currents

Harmonic Order	Maximum Permissible Harmonic Current (Ampere)	Harmonic Order	Maximum Permissible Harmonic Current (Ampere)
Odd Harmonic		Even Harmonic	
3	2.30	2	1.08
5	1.14	4	0.43
7	0.77	6	0.30
9	0.40	$8 \leq n \leq 40$	$0.23 \times 8/n$
11	0.33		
13	0.21		
$15 \leq n \leq 39$	$0.15 \times 15/n$		

4.4 Test Procedure

The EUT is supplied in series with power analyzer from a power source has the same normal voltage and frequency as the rated supply voltage and the equipment under test. The rated voltage at the supply voltage of EUT of 0.94 times and 1.06 times shall be performed.

4.5 Test Specification

According to EN 61000-3-2/2000, EN 61000-3-3/1995

4.6 Test Result

The measurement of the power harmonics, which test at the extremes of EUT's supply range, was investigated and the test result was shown on the Appendix A. The acceptance criterion was met and the EUT has pass the measurement.


5. Electrostatic Discharge (ESD)

5.1 Test Equipment List

No.	Instrument	Manufacture	Model	Serial No.	Last Calibrate
1.	ESD Emulator	Noiseken	ESS-100L	0199C02380	Mar. 02, 2002

Remark: All equipment upon which need to calibrated are with calibration period of one year.

5.2 Test Setup



5.3 Test Level

Item	Environment	Unit	Test Specification	Performance Criteria
Enclosure Room	Electrostatic Discharge	KV(Charge Voltage)	8 (Air Discharge) 4 (Contact Discharge)	B

5.4 Test Procedure

Direct applicant of discharge to the EUT:

Contact discharge was applied only to the conducted surfaces of the EUT.

Air discharge was applied only to the non-conductive surfaces of the EUT.

When the measurement was taken, The ESD discharger was performed in single discharge. For the single discharge time between successive single discharges will keep on one second. It was at least ten single discharges with positive and negative at the same selected pointed. The selected pointed, which was performed with electrostatic discharge, was marked on the red label on the EUT.

Indirect applicant of discharge to the EUT:

Vertical Coupling Plane (VCP)

The coupling plane, of dimensions 0.5m x 0.5m, is placed parallel to , and positioned at a distance 0.1m from, the EUT, with the discharge electrode touching the coupling plane.

The four faces of the EUT will be performed with electrostatic discharge. It was at least ten single discharges with positive and negative at the same selected point.

Horizontal Coupling Plane (HCP)

The coupling plane is placed under the EUT. The generator shall be positioned vertically at a distance of 0.1m from the EUT, with the discharge electrode touching the coupling.

The four faces of the EUT will be performed with electrostatic discharge. It was at least ten single discharges with positive and negative at the same selected pointed.

5.5 Test Specification

According to EN 61000-4-2/1998

5.6 Test Result

The measurement of the electrostatic discharge was investigated and the test result was shown on the Appendix A. The acceptance criterion was met and the EUT has passed the measurement.

6.3 Test Procedure

The EUT and load, which are placed on a wooden table that the height is 0.8 meter above ground, are placed with one coincident with the calibration plane such that the distance from antenna to the EUT is 3 meters.

Both horizontal and vertical polarization of the antenna position and four sides of the EUT are set on measurement.

In order to judge the EUT performance, a CCD camera is used to monitor the situation of EUT. All the scanning conditions are as follows:

Condition of Test	Remarks
EN 61000-4-3/1998	
1. Field Strength	3V/M; Level 2
2. Radiated Signal	AM 80% modulated with 1KHz
3. Scanning Frequencies	80MHz ~ 1000MHz
4. Dwell Time	3 seconds
5. Frequency step size Δf	1%
6. The rate of swept of frequency	1.5×10^{-3} decades/s

6.4 Specification

According to EN 61000-4-3/1998

6.5 Test Result

The measurement of the radiated susceptibility was investigated and the test result was shown on the appendix A. The acceptance criterion was met and the EUT has passed the measurement.


7 Electrical Fast Transient/Burst (EFT/B)

7.1 Test Equipment List

No.	Instrument	Manufacture	Model	Serial No.	Last Calibrate
1.	EMC Test System	EMC Partner	Transient-1000	TR1000-341	Aug 15, 2001
2.	Absorbing Clamp	EMC Partner	Transient-1000	CNEFT1000-176	Aug 15, 2001

Remark: All equipment upon which need to calibrated are with calibration period of one year.

7.2 Test Setup



7.3 Test Level

Item	Environment	Unit	Test Specification	Performance Criteria
Ports for signal Lines and Control Lines				B
	Fast Transients Common Mode	KV (Peak)	0.5	
		Tr/Ts (ns)	5/50	
		Rep. Frequency (KHz)	5	
DC Input and DC Output Power Ports				B
	Fast Transients Common Mode	KV (Peak)	0.5	
		Tr/Ts (ns)	5/50	
		Rep. Frequency (KHz)	5	
Input and Output AC Power Ports				B
	Fast Transients Common Mode	KV (Peak)	1	
		Tr/Ts (ns)	5/50	
		Rep. Frequency (KHz)	5	
Functional Earth Ports				B
	Fast Transients Common Mode	KV (Peak)	0.5	
		Tr/Ts (ns)	5/50	
		Rep. Frequency (KHz)	5	

7.4 Test Procedure

The EUT and load are placed on a wooden table that is 0.8meter height above a metal ground plane dimension is 1m x 1m and thickness is at least 0.2mm. It also projected beyond the EUT by at lease 0.1meter on all sides.

For Input and Output AC power or DC Input and DC Output Power Ports:

The EUT is connected with the power mains through a coupling device that directly couples the EFT interference signal.

Each of the line and nature conductors is impressed with burst noise for 1 minute.

For Functional Earth Port:

The EUT is connected to the power mains through a coupling device that directly couples the EFT interference signal.

The protective earth line (PE) is impressed with burst noise for 1 minute.

The length of power cord between the coupling device and the EUT shall be 1 meter.

For signal Lines and Control Lines Test:

The EFT interference signal is through a coupling clamp device couples to the signal and control lines of the EUT with burst noise for 1 minute.

7.5 Test Specification

According to EN 61000-4-4/1995

7.6 Test Result

The measurement of the Electrical Fast Transient/Burst was investigated and test result was shown on the appendix A. The acceptance criterion was met and the EUT has passed the measurement.


8. Surge

8.1 Test Equipment List

No	Instrument	Manufacture	Model	Serial No.	Last Calibrate
1.	EMC Test System	EMC Partner	Transient-1000	TR1000-341	Aug 15, 2001

Remark: All equipment upon which need to calibrated are with calibration period of one year.

8.2 Test Setup



8.3 Test Level

Item	Environment	Unit	Test Specification	Performance Criteria
Dc Input and DC Output Power Ports				
	Surge	Tr/Ts (μ s)	1.2/50(8/20)	B
	Line to Ground	KV	± 0.5	
	Line to Line	KV	± 0.5	
AC Input and Ac Output Power Ports				
	Surge	Tr/Ts (μ s)	1.2/50(8/20)	B
	Line to Ground	KV	± 2	
	Line to Line	KV	± 1	

8.4 Test Procedure

The EUT and its load are placed on a table which is 0.8 meter height above a metal ground plane dimension is 1 meter x 1 meter and the thickness is 0.5 mm. It's also projected beyond the EUT at least 0.1 meter on all sides. The length of power cord between the coupling device and the EUT shall be 2meter or less.

For Input and Output AC Power or DC Input and Dc Output Power Ports:

The EUT is connected to the power mains through a coupling device that directly couples the Surge interference signal.

The Surge noise shall be applied synchronized to the voltage phase at 0°, 90°, 180°, 270° and the peak value of the AC voltage wave. (Positive and Negative)

Each of line-earth and line-line is impressed with a sequence of five surge voltages with interval of 1 minute.

8.5 Test Specification

According to EN 61000-4-5/1995

8.6 Test Result

The Measurement of the Surge was investigated and the test result was shown on the appendix A. The acceptance criterion was met and the EUT has passed the test.


9. Conducted Susceptibility

9.1 Test Equipment List

No.	Instrument	Manufacture	Model	Serial No.	Last Calibrate
1.	Signal Generator	Rohde & Schwarz	SMY 02	845069/018	May 02, 2001
2.	Power Amplifier	Amplifier Research	100W1000M1A	20638	May 01, 2001
4.	Directional Coupler	Amplifier Research	DC2600	20508	Aug 23, 2001
5.	CDN	FCC	FCC-801-M3-25A	9993	Aug 23, 2001

Remark: All equipment upon which need to calibrated are with calibration period of one year.

9.2 Test Setup



9.3 Test Level

Item	Environment	Unit	Test Specification	Performance Criteria
Ports for Signal Lines and Data Buses, not involved in process control, etc.				
	Radio-Frequency	MHz	0.15 ~ 80	A
	Common Mode	V (rms, Unmodulated)	3	
	Amplitude Modulated	%AM (1KHz)	80	
		Source Impedance	150	
Ac Input and AC Output and DC Input and DC output Ports and Functional Earth Ports				
	Radio-Frequency	MHz	0.15 ~ 80	A
	Common Mode	V (rms, Unmodulated)	3	
	Amplitude Modulated	%AM (1KHz)	80	
		Source Impedance	150	

9.4 Test Procedure

The EUT are placed on a table which is 0.8meter height and a ground reference plane on the table, the EUT are placed upon table and use a 10cm insulation between the EUT and ground reference plane.

For AC Input and AC Output Power or DC Input and DC Output Power Ports:
The EUT is connected to the power mains through a coupling and decoupling networks for power supply lines. It also directly couples the disturbance signal into EUT.
Use CDN-M2 for two wires or CDN-3 for three wires.

For Signal Lines Lines and Control Lines Test:
The disturbance signal is through a coupling and decoupling networks (CDN) or EM-clamp device couples to the signal and control lines of the EUT.

All scanning frequencies conditions are as following:

Condition of Test	Remarks:
1. Field Strength	130dB μ V (3V), Level 2
2. Radiated Signal	AM 80% modulated with 1KHz
3. Scanning frequencies	0.15MHz ~ 80MHz
4. Dwell Time	3 seconds
5. Frequency step size Δf	1%
6. The rate of Swept of Frequency	1.5×10^{-3} decades/s

9.5 Test Specification

According to EN 61000-4-6/1996

9.6 Test Result

The Measurement of the Conducted Susceptibility was investigated and the test result was shown on the appendix A. The acceptance criterion was met and the EUT has passed the test.


10 Power Frequency Magnetic Field

10.1 Test Equipment List

No.	Instrument	Manufacture	Model	Serial No.	Last Calibrate
1.	EMC Test System	EMC Partner	Transient-1000	TR1000-341	Aug 15, 2001
2.	Magnetic Coil	EMC Partner	MF-1000	MF1000-1-51	Aug 15, 2001

Remark: All equipment upon which need to calibrated are with calibration period of one year.

10.2 Test Setup



10.3 Test Level

Item	Environment	Unit	Test Specification	Performance Criteria
Enclosure Room				
Power-Frequency		50	Hz	A
Magnetic Field		3	A/M	

10.4 Test Procedure

The EUT and its load are placed on a table that is 0.8 meter above the metal ground plane dimension is at least 1 meter x 1 meter. The test magnetic field shall be placed at least than 3 meters distance from the induction coil.

The test magnetic field shall be applied by the immersion method to the EUT. The induction coil shall be rotated by 90° in order to expose the EUT to the test field with different orientation (X, Y, Z orientation).

10.5 Test Specification

According to EN 61000-4-8/1993

10.6 Test Result

The Measurement of the Power Frequency Magnetic Field was investigated and the test result was shown on the appendix A. The acceptance criterion was met and the EUT has passed the test.


11. Voltage Dips and Interruption Measurement

11.1 Test Equipment List

No.	Instrument	Manufacture	Model	Serial No.	Last Calibrate
1.	EMC Test System	EMC Partner	Transient-1000	TR1000-341	Aug 15, 2001

Remark: All equipment upon which need to calibrated are with calibration period of one year.

11.2 Test setup



11.3 Test Level

Item	Environment	Unit	Test Specification	Performance Criteria
Ac Input and AC Output Power Ports	Voltage Dips		30% Reduction	B
			500ms	
	Voltage Interruption		>95% Reduction	C
			10ms	
			>95% Reduction	C
			5000ms	

11.4 Test Procedure

The EUT and its load are placed on a wooden table which is 0.8 meter above a metal ground plane which dimension is 1 meter x 1 meter, the thickness is 0.65mm. It projected beyond the EUT by at least 0.1 meter on all sides. The power cord shall be used the shortest power cord as specified by the manufacturer.

For Voltage Dips / Interruption Test:

The EUT is connected to the power mains through a coupling device that directly couples to the Voltage Dips and Interruption Generator.

The EUT shall be tested for 30% voltage dips of supplied voltage and duration time is 500ms, for 95% voltage dips of supplied voltage and duration time is 500ms with a sequence of three voltage dips with intervals of 10 seconds, and for 95% voltage interruption of supplied voltage and the duration time is 5000ms with a sequence of three voltage interruptions with intervals of 10 seconds.

Voltage phase shifting are shall occur at 0°, 45°, 90°, 135°, 180°, 225°, 270°, 315° of the voltage.

11.5 Test Specification

According to EN 61000-4-11/1994

11.6 Test Result

The Measurement of the Voltage Dips and Interruption was investigated and the test result was shown on the appendix A. The acceptance criterion was met and the EUT has passed the test.

12 Modification List for EMC Complying Test

The modification is solely made by the applicant

13 Appendix

Appendix A: Summary of Test Result

Appendix B: The test photograph of EUT

Appendix C: The Detail Photograph of EUT

Appendix A: Summary of Test Result

The test result in the emission and immunity were performed according to the requirement of measurement standard and procedures. Best Laboratory is assumed full responsibility for the accuracy and completeness of these measurements. The Test data of the emissions and immunity are listed as the appendix data.

All these tests are were carried out with the EUT in normal operation, which was defined as:

******* EMC Test Result: The EUT has been passed the all measurements. *******

The uncertainty is calculated in accordance with NAMAS NIS 81, the total uncertainty for this test is as follows:

⇒ Emission Test

- | | |
|--|---------|
| * Uncertainty in the Conducted Emission Test: | <±2.0dB |
| * Uncertainty in the Field Strength measurement: | <±4.0dB |

Conducted Emission Test

Date Measurement Performed: Mar. 14, 2002

EUT : Industrial PC

Testing Mode : 640 X 480MHz, LAN=10MHz

Temperature : 24°C

Humidity : 69%RH

Line 1:

Frequency (KHz)	Corrected Amplitude (dBμV)			Limit (dBμV)		Margin dB
	Peak	QP	Avg.	QP	Avg.	
154.2500	47.11	***	***	79.00	66.00	-18.89
195.9000	43.87	***	***	79.00	66.00	-22.13
291.1000	31.12	***	***	79.00	66.00	-34.88
580..1000	28.66	***	***	73.00	60.00	-31.37
2510.0000	30.41	***	***	73.00	60.00	-29.59
5035.0000	42.02	***	***	73.00	60.00	-17.98
7920.0000	36.24	***	***	73.00	60.00	-23.76
11992.0000	48.22	***	***	73.00	60.00	-11.78
14568.0000	41.37	***	***	73.00	60.00	-18.63
21848.0000	38.15	***	***	73.00	60.00	-21.85

Line 2:

Frequency (KHz)	Corrected Amplitude (dBμV)			Limit (dBμV)		Margin dB
	Peak	QP	Avg.	QP	Avg.	
150.0000	47.72	***	***	79.00	66.00	-18.28
193.3500	47.30	***	***	79.00	66.00	-18.70
291.1000	37.23	***	***	79.00	66.00	-28.77
483.2000	36.68	***	***	79.00	66.00	-29.32
966.0000	30.34	***	***	73.00	60.00	-29.66
2515.0000	32.12	***	***	73.00	60.00	-27.88
5035.0000	41.48	***	***	73.00	60.00	-18.52
12000.0000	48.33	***	***	73.00	60.00	-11.67
14584.0000	41.89	***	***	73.00	60.00	-18.11
21880.0000	39.31	***	***	73.00	60.00	-20.69

*** Remark: The above corrected amplitudes are all under the average limit. ***

Conducted Emission Test

Date Measurement Performed: Mar. 14, 2002

EUT : Industrial PC

Testing Mode : 1024 X 768MHz, LAN=10MHz

Temperature : 24°C

Humidity : 69%RH

Line 1:

Frequency (KHz)	Corrected Amplitude (dBμV)			Limit (dBμV)		Margin dB
	Peak	QP	Avg.	QP	Avg.	
150.0000	46.95	***	***	79.00	66.00	-19.05
194.2000	44.77	***	***	79.00	66.00	-21.23
289.4000	31.68	***	***	79.00	66.00	-34.32
484.0500	30.40	***	***	79.00	66.00	-35.60
2125.0000	28.13	***	***	73.00	60.00	-31.87
6496.0000	35.07	***	***	73.00	60.00	-24.93
8008.0000	35.09	***	***	73.00	60.00	-24.91
12000.0000	47.69	***	***	73.00	60.00	-12.31
14560.0000	41.69	***	***	73.00	60.00	-18.31
21848.0000	38.19	***	***	73.00	60.00	-21.81

Line 2:

Frequency (KHz)	Corrected Amplitude (dBμV)			Limit (dBμV)		Margin dB
	Peak	QP	Avg.	QP	Avg.	
150.8500	47.74	***	***	79.00	66.00	-18.26
194.2000	48.11	***	***	79.00	66.00	-17.89
291.1000	37.99	***	***	79.00	66.00	-28.01
484.0500	37.70	***	***	79.00	66.00	-28.30
2030.0000	30.66	***	***	73.00	60.00	-29.34
6096.0000	34.45	***	***	73.00	60.00	-25.55
11992.0000	48.30	***	***	73.00	60.00	-11.70
14560.0000	41.02	***	***	73.00	60.00	-18.98
16624.0000	38.89	***	***	73.00	60.00	-21.11
21832.0000	39.95	***	***	73.00	60.00	-20.05

*** Remark: The above corrected amplitudes are all under the average limit. ***

Conducted Emission Test

Date Measurement Performed: Mar. 14, 2001

EUT : Industrial PC

Testing Mode : 1600 X 1200MHz, LAN=10MHz

Temperature : 24°C

Humidity : 69%RH

Line 1:

Frequency (KHz)	Corrected Amplitude (dBμV)			Limit (dBμV)		Margin dB
	Peak	QP	Avg.	QP	Avg.	
150.8500	47.11	***	***	79.00	66.00	-18.89
194.2000	43.87	***	***	79.00	66.00	-22.13
291.1000	30.39	***	***	79.00	66.00	-35.61
581.8000	28.35	***	***	73.00	60.00	-31.65
2030.0000	29.45	***	***	73.00	60.00	-30.55
6584.0000	36.02	***	***	73.00	60.00	-23.98
11992.0000	46.83	***	***	73.00	60.00	-13.17
14560.0000	41.05	***	***	73.00	60.00	-18.95
16616.0000	38.52	***	***	73.00	60.00	-21.48
21848.0000	38.95	***	***	73.00	60.00	-21.05

Line 2:

Frequency (KHz)	Corrected Amplitude (dBμV)			Limit (dBμV)		Margin dB
	Peak	QP	Avg.	QP	Avg.	
155.9500	45.66	***	***	79.00	66.00	-20.34
194.2000	48.31	***	***	79.00	66.00	-17.69
291.1000	37.70	***	***	79.00	66.00	-28.30
484.0500	37.09	***	***	79.00	66.00	-28.91
2030.0000	31.59	***	***	73.00	60.00	-28.41
5690.0000	34.18	***	***	73.00	60.00	-25.82
7976.0000	36.73	***	***	73.00	60.00	-23.27
11992.0000	47.30	***	***	73.00	60.00	-12.70
14576.0000	41.58	***	***	73.00	60.00	-18.42
21840.0000	38.45	***	***	73.00	60.00	-21.55

*** Remark: The above corrected amplitudes are all under the average limit. ***

Conducted Emission Test

Date Measurement Performed: Mar. 14, 2001

EUT : Industrial PC

Testing Mode : 640 X 480MHz, LAN=100MHz

Temperature : 24°C

Humidity : 69%RH

Line 1:

Frequency (KHz)	Corrected Amplitude (dBμV)			Limit (dBμV)		Margin dB
	Peak	QP	Avg.	QP	Avg.	
155.1000	45.68	***	***	79.00	66.00	-20.32
195.0500	44.86	***	***	79.00	66.00	-21.14
289.4000	31.24	***	***	79.00	66.00	-34.76
581.8000	28.94	***	***	73.00	60.00	-31.06
2510.0000	31.50	***	***	73.00	60.00	-28.50
5035.0000	41.15	***	***	73.00	60.00	-18.85
7920.0000	40.94	***	***	73.00	60.00	-19.06
12000.0000	48.64	***	***	73.00	60.00	-11.36
14568.0000	41.78	***	***	73.00	60.00	-18.22
21848.0000	38.47	***	***	73.00	60.00	-21.53

Line 2:

Frequency (KHz)	Corrected Amplitude (dBμV)			Limit (dBμV)		Margin dB
	Peak	QP	Avg.	QP	Avg.	
153.4000	46.95	***	***	79.00	66.00	-19.05
194.2000	48.30	***	***	79.00	66.00	-17.70
290.2500	37.19	***	***	79.00	66.00	-28.81
484.0500	36.68	***	***	79.00	66.00	-29.32
2510.0000	32.75	***	***	73.00	60.00	-27.25
5035.0000	41.57	***	***	73.00	60.00	-18.43
7976.0000	38.14	***	***	73.00	60.00	-21.86
11992.0000	48.34	***	***	73.00	60.00	-11.66
16224.0000	41.73	***	***	73.00	60.00	-18.27
21880.0000	37.77	***	***	73.00	60.00	-22.23

*** Remark: The above corrected amplitudes are all under the average limit. ***

Conducted Emission Test

Date Measurement Performed: Mar. 14, 2002

EUT : Industrial PC

Testing Mode : 1024 X 768MHz, LAN=100MHz

Temperature : 24°C

Humidity : 69%RH

Line 1:

Frequency (KHz)	Corrected Amplitude (dBμV)			Limit (dBμV)		Margin dB
	Peak	QP	Avg.	QP	Avg.	
151.7000	47.23	***	***	79.00	66.00	-18.77
193.3500	44.53	***	***	79.00	66.00	-21.47
291.1000	31.63	***	***	79.00	66.00	-34.37
483.2000	30.12	***	***	79.00	66.00	-35.88
1255.0000	26.36	***	***	73.00	60.00	-33.64
2415.0000	28.02	***	***	73.00	60.00	-31.98
7920.0000	40.20	***	***	73.00	60.00	-19.80
11992.0000	48.55	***	***	73.00	60.00	-11.45
16224.0000	41.20	***	***	73.00	60.00	-18.80
21848.0000	37.76	***	***	73.00	60.00	-22.24

Line 2:

Frequency (KHz)	Corrected Amplitude (dBμV)			Limit (dBμV)		Margin dB
	Peak	QP	Avg.	QP	Avg.	
153.4000	46.44	***	***	79.00	66.00	-19.56
194.2000	49.00	***	***	79.00	66.00	-17.00
291.1000	37.75	***	***	79.00	66.00	-28.25
484.0500	37.16	***	***	79.00	66.00	-28.84
966.8500	30.91	***	***	73.00	60.00	-29.09
2030.0000	30.86	***	***	73.00	60.00	-29.14
6496.0000	34.43	***	***	73.00	60.00	-25.57
7920.0000	39.99	***	***	73.00	60.00	-20.01
12000.0000	48.75	***	***	73.00	60.00	-11.25
16224.0000	43.69	***	***	73.00	60.00	-16.31

*** Remark: The above corrected amplitudes are all under the average limit. ***

Conducted Emission Test

Date Measurement Performed: Mar. 14, 2002

EUT : Industrial PC

Testing Mode : 1600 X 1200MHz, LAN=100MHz

Temperature : 24°C

Humidity : 69%RH

Line 1:

Frequency (KHz)	Corrected Amplitude (dBμV)			Limit (dBμV)		Margin dB
	Peak	QP	Avg.	QP	Avg.	
152.5500	46.91	***	***	79.00	66.00	-19.09
194.2000	44.86	***	***	79.00	66.00	-21.14
292.8000	30.73	***	***	79.00	66.00	-35.27
376.9500	33.28	***	***	79.00	66.00	-32.72
582.6500	28.45	***	***	73.00	60.00	-31.55
1645.0000	27.94	***	***	73.00	60.00	-32.06
6304.0000	33.03	***	***	73.00	60.00	-26.97
7920.0000	38.26	***	***	73.00	60.00	-21.74
11992.0000	48.83	***	***	73.00	60.00	-11.17
21856.0000	38.27	***	***	73.00	60.00	-21.73

Line 2:

Frequency (KHz)	Corrected Amplitude (dBμV)			Limit (dBμV)		Margin dB
	Peak	QP	Avg.	QP	Avg.	
150.0000	47.79	***	***	79.00	66.00	-18.21
194.2000	48.70	***	***	79.00	66.00	-17.30
291.1000	37.27	***	***	79.00	66.00	-28.73
484.0500	37.12	***	***	79.00	66.00	-28.88
677.0000	30.80	***	***	73.00	60.00	-29.20
1355.0000	30.73	***	***	73.00	60.00	-29.27
2030.0000	30.90	***	***	73.00	60.00	-29.10
7920.0000	38.74	***	***	73.00	60.00	-21.26
11992.0000	48.94	***	***	73.00	60.00	-11.06
21848.0000	37.95	***	***	73.00	60.00	-22.05

*** Remark: The above corrected amplitudes are all under the average limit. ***

Field Strength Test

Date Measurement Performed: Mar. 15, 2002

EUT : Industrial PC

Testing Mode : 1024 X 768MHz, LAN=10MHz

Polarity : Vertical

Temperature : 26°C

Humidity : 73%RH

Frequency (MHz)	Reading Amplitude (dBμV/m)	Table Degree (°)	Antenna Height (Meter)	Correction Factor (dB/m)	Corrected Amplitude (dBμV/m)	Limit (dBμV/m)	Margin (dB)
74.803	23.17	339	1.00	7.60	30.77	40.00	-9.23
132.977	20.44	232	1.00	12.26	32.70	40.00	-7.30
166.221	19.63	184	1.00	10.54	30.17	40.00	-9.83
264.011	22.50	196	1.00	14.48	36.98	47.00	-10.01
299.199	16.02	198	1.00	14.44	30.46	47.00	-16.54

Remark:

1. The “ Correction Factor “ contains antenna factor, cable loss.
2. The formula of “ Corrected Amplitude “ is as follow”
 Reading Amplitude + Correction Factor = Corrected Amplitude.

Field Strength Measurement

Date Measurement Performed: Mar. 15, 2002

EUT : Industrial PC

Testing Mode : 1600 X 1200MHz, LAN=10MHz

Polarity : Horizontal

Temperature : 24°C

Humidity : 79%RH

Frequency (MHz)	Reading Amplitude (dBμV/m)	Table Degree (°)	Antenna Height (Meter)	Correction Factor (dB/m)	Corrected Amplitude (dBμV/m)	Limit (dBμV/m)	Margin (dB)
41.555	12.82	138	3.99	12.42	25.24	40.00	-14.76
74.799	18.87	96	3.99	7.60	26.47	40.00	-13.53
264.009	17.18	267	2.47	14.48	31.66	47.00	-15.34
624.997	3.19	40	1.43	20.92	24.11	47.00	-22.89

Remark:

1. The “ Correction Factor “ contains antenna factor, cable loss.
2. The formula of “ Corrected Amplitude “ is as follow”
 Reading Amplitude + Correction Factor = Corrected Amplitude.

Power Harmonic / Fluctuation Test**Power Harmonic:**

Operating Environment:

Temperature : 26°C
 Humidity : 68%RH
 Atmosp

Power Harmonic / Fluctuation Test**Power Harmonic:**

Operating Environment:

Temperature : 26°C
 Humidity : 68%RH
 Atmosphere : 1010mBar

Test Condition:

EUT Position : Table Top

Result:

Summary of the test result: Pass

Fluctuation Test:

Test Frequency : 50Hz
 Test Time : 10 min.

Test Voltage : 230VAC
 Tshort : 5.0 min

EUT	Data	Limit	Result	Test Enable
Pst	0.001	1.00	Pass	True
Plt	0.001	0.65	Pass	True
dc %	0.00	3.00	Pass	True
dmax %	0.00	4.00	Pass	True
d(t) sec	0.00	0.20	Pass	True

Power Source Data

Source Pst max	0.022	0.400	Pass	True
% THD	0.02	3.00	Pass	True

Electrostatic Discharge Test

Item	Amount of Discharge	Voltage	Required Criteria	Complied to Criteria	Results
Air Discharge	10	+2KV	B	B	Pass
	10	-2KV	B	B	Pass
	10	+4KV	B	B	Pass
	10	-4KV	B	B	Pass
	10	+8KV	B	B	Pass
	10	-8KV	B	B	Pass
Contact Discharge	25	+2KV	B	B	Pass
	25	-2KV	B	B	Pass
	25	-4KV	B	B	Pass
	25	-4KV	B	B	Pass
Indirect Discharge	25	+2KV	B	B	Pass
	25	-2KV	B	B	Pass
	25	+4KV	B	B	Pass
	25	-4KV	B	B	Pass

Remark:

- ☐ Criteria A: Operation as intended during and after the measurement
- ☒ Criteria B: Operation as Intended after the test
- ☐ Criteria C: Malfunction during and after, need manual reset
- ☐ Criteria D: The sample is damaged

Radiated Susceptibility

Frequency (MHz)	Position (Angle)	Polarity (H or V)	Voltage (V/m)	Required Criteria	Complied Criteria	Result
80 ~ 1000	0	H	3	A	A	Pass
80 ~ 1000	0	V	3	A	A	Pass
80 ~ 1000	90	H	3	A	A	Pass
80 ~ 1000	90	V	3	A	A	Pass
80 ~ 1000	180	H	3	A	A	Pass
80 ~ 1000	180	V	3	A	A	Pass
80 ~ 1000	270	H	3	A	A	Pass
80 ~ 1000	270	V	3	A	A	Pass

Remark:

- (X) Criteria A: Operation as intended during and after the measurement
- () Criteria B: Operation as Intended after the test
- () Criteria C: Malfunction during and after, need manual reset
- () Criteria D: The sample is damaged

Electrical Fast Transient / Burst

Inject Line	Polarity	Voltage (KV)	Inject Time (Second)	Inject Method	Required Criteria	Complied Criteria	Result
L	±	1.0KV	60	Direct	B	B	Pass
	±	2.0KV	60	Direct	B	B	Pass
N	±	1.0KV	60	Direct	B	B	Pass
	±	2.0KV	60	Direct	B	B	Pass
PE	±	1.0KV	60	Direct	B	B	Pass
	±	2.0KV	60	Direct	B	B	Pass
L+N	±	1.0KV	60	Direct	B	B	Pass
	±	2.0KV	60	Direct	B	B	Pass
L+PE	±	1.0KV	60	Direct	B	B	Pass
	±	2.0KV	60	Direct	B	B	Pass
N+PE	±	1.0KV	60	Direct	B	B	Pass
	±	2.0KV	60	Direct	B	B	Pass
L+N+PE	±	1.0KV	60	Direct	B	B	Pass
	±	2.0KV	60	Direct	B	B	Pass
Clamp	±	0.5KV	60	Couple	B	B	Pass
	±	1.0KV	60	Couple	B	B	Pass

Remark:

- ☐ Criteria A: Operation as intended during and after the measurement
☒ Criteria B: Operation as Intended after the test
☐ Criteria C: Malfunction during and after, need manual reset
☐ Criteria D: The sample is damaged

Surge Test

Inject Line	Polarity	Angle	Voltage (KV)	Inject Time (Second)	Inject Method	Required Criteria	Complied Criteria	Result
L+N	±	0	0.5KV	60	Direct	B	B	Pass
L+N	±	90	0.5KV	60	Direct	B	B	Pass
L+N	±	180	0.5KV	60	Direct	B	B	Pass
L+N	±	270	0.5KV	60	Direct	B	B	Pass
L+N	±	0	1.0KV	60	Direct	B	B	Pass
L+N	±	90	1.0KV	60	Direct	B	B	Pass
L+N	±	180	1.0KV	60	Direct	B	B	Pass
L+N	±	270	1.0KV	60	Direct	B	B	Pass
L+PE	±	0	0.5KV	60	Direct	B	B	Pass
L+PE	±	90	0.5KV	60	Direct	B	B	Pass
L+PE	±	180	0.5KV	60	Direct	B	B	Pass
L+PE	±	270	0.5KV	60	Direct	B	B	Pass
L+PE	±	0	1.0KV	60	Direct	B	B	Pass
L+PE	±	90	1.0KV	60	Direct	B	B	Pass
L+PE	±	180	1.0KV	60	Direct	B	B	Pass
L+PE	±	270	1.0KV	60	Direct	B	B	Pass
L+PE	±	0	2.0KV	60	Direct	B	B	Pass
L+PE	±	90	2.0KV	60	Direct	B	B	Pass
L+PE	±	180	2.0KV	60	Direct	B	B	Pass
L+PE	±	270	2.0KV	60	Direct	B	B	Pass
N+PE	±	0	0.5KV	60	Direct	B	B	Pass
N+PE	±	90	0.5KV	60	Direct	B	B	Pass
N+PE	±	180	0.5KV	60	Direct	B	B	Pass
N+PE	±	270	0.5KV	60	Direct	B	B	Pass
N+PE	±	0	1.0KV	60	Direct	B	B	Pass
N+PE	±	90	1.0KV	60	Direct	B	B	Pass
N+PE	±	180	1.0KV	60	Direct	B	B	Pass
N+PE	±	270	1.0KV	60	Direct	B	B	Pass
N+PE	±	0	2.0KV	60	Direct	B	B	Pass
N+PE	±	90	2.0KV	60	Direct	B	B	Pass
N+PE	±	180	2.0KV	60	Direct	B	B	Pass
N+PE	±	270	2.0KV	60	Direct	B	B	Pass

Remark:

- ☐ Criteria A: Operation as intended during and after the measurement
- ☒ Criteria B: Operation as Intended after the test
- ☐ Criteria C: Malfunction during and after, need manual reset
- ☐ Criteria D: The sample is damaged

Conducted Susceptibility

Inject Line	Field Strength dB μ V (V)	Inject Method	Required Criteria	Complied Criteria	Result
AC Line	130(3V)	CDN	A	A	Pass
Data Cable	130(3V)	CDN	A	A	Pass

Remark:

- ☒ Criteria A: Operation as intended during and after the measurement
- ☐ Criteria B: Operation as Intended after the test
- ☐ Criteria C: Malfunction during and after, need manual reset
- ☐ Criteria D: The sample is damaged

Power Frequency Magnetic Field Test

Polarization	Frequency (Hz)	Magnetic Strength (A/M)	Required Criteria	Complied Criteria	Result
X Orientation	50	1	A	A	Pass
Y Orientation	50	1	A	A	Pass
Z Orientation	50	1	A	A	Pass

Remark:

- ☒ Criteria A: Operation as intended during and after the measurement
- ☐ Criteria B: Operation as Intended after the test
- ☐ Criteria C: Malfunction during and after, need manual reset
- ☐ Criteria D: The sample is damaged

Voltage Dips and Interruption Test

Voltage Dips and Interruption Reduction (%)	Angle (Degree)	Test Duration (ms)	Required Criteria	Complied Criteria	Result
DIP					
30	0	500	B	B	Pass
30	45	500	B	B	Pass
30	90	500	B	B	Pass
30	135	500	B	B	Pass
30	180	500	B	B	Pass
30	225	500	B	B	Pass
30	270	500	B	B	Pass
30	315	500	B	B	Pass
>95	0	10	C	C	Pass
>95	45	10	C	C	Pass
>95	90	10	C	C	Pass
>95	135	10	C	C	Pass
>95	180	10	C	C	Pass
>95	225	10	C	C	Pass
>95	270	10	C	C	Pass
>95	315	10	C	C	Pass
Interruption					
>95	0	5000	C	C	Pass
>95	45	5000	C	C	Pass
>95	90	5000	C	C	Pass
>95	135	5000	C	C	Pass
>95	180	5000	C	C	Pass
>95	225	5000	C	C	Pass
>95	270	5000	C	C	Pass
>95	315	5000	C	C	Pass

Remark:

- () Criteria A: Operation as intended during and after the measurement
- (X) Criteria B: Operation as Intended after the test (Test Mode: 30%)
- (X) Criteria C: Malfunction during and after, need manual reset(Test Mode: 60%, >95%)
- () Criteria D: The sample is damaged

Appendix B: The Test Photograph of EUT


The Photograph of Conducted Emission Test --- Mains Port



The Photograph of Radiated Emission Test



The Photograph of Radiation Susceptibility Test



The Photograph of Electrical Fast Transient/Burst Test



The Photograph of Electrostatic Discharge Test



The Photograph of Surge Test



The Photograph of Conducted Susceptibility Test



The Photograph of Power Frequency Magnetic Field Test



The Photograph of Voltage Dips and Interruption Test





Appendix C: The Detail Photograph of EUT
























TE07-276-25037



Seasonic SSH-250G
SWITCHING POWER SUPPLY



INPUT:
~100-120VAC/ 6A 50/60Hz
~200-240VAC/ 4A 50/60Hz



OUTPUT:

DC	+5V	+12V	-5V	-12V
250W	25A	1.0A	0.3A	0.3A

AC Outlet Receptacle (Switched) ~100-120VAC 1A max
~200-240VAC 1A max



Umgebungs - Temperatur: 50°C max
Ambient Temperature: 50°C max

ACHTUNG Gefährliche spannungen!
CAUTION Hazardous Area!

- Gehäuse nicht öffnen
 - Do not remove this cover
 - Vor Anschluss Eingangsspannung überprüfen
 - Check input voltage before plug in
 - Lüftungsöffnung nicht abdecken
 - Air opening should not be covered
- Comply to EN60950/IEC950

See Seasonic Electronic Co., Ltd. (CN)



Better Quality with
Temperature Controlled Fan &
Conform to DSP Vtg. 243 (II)