



CE EMC

TEST REPORT

For

Universal Network Controller

Model: UNO-1019

Trade Name: Advantech

Issued for

Advantech Co., Ltd.

**No. 1, Alley 20, Lane 26, Rueiguang Road, Neihu District,
Taipei 114, Taiwan, R.O.C.**

Issued by

Compliance Certification Services Inc.

**No. 81-1, Lane 210, Pa-De 2nd Rd., Luchu Hsiang,
Taoyuan Shien, (338) Taiwan, R.O.C.**

TEL: 886-3-324-0332

FAX: 886-3-324-5235



***Note:** This report shall not be reproduced except in full, without the written approval of Compliance Certification Services Inc. Ltd. This document may be altered or revised by Compliance Certification Services Inc. personnel only, and shall be noted in the revision section of the document.*



TABLE OF CONTENTS

1	TEST RESULT CERTIFICATION.....	3
2	EUT DESCRIPTION.....	4
3	TEST METHODOLOGY	5
3.1	EUT SYSTEM OPERATION	5
3.2	DECISION OF FINAL TEST MODE.....	5
4	SETUP OF EQUIPMENT UNDER TEST.....	6
5	FACILITIES AND ACCREDITATIONS.....	6
5.1	FACILITIES	6
5.2	LABORATORY ACCREDITATIONS AND LISTINGS	7
6	INSTRUMENT AND CALIBRATION	8
6.1	MEASURING INSTRUMENT CALIBRATION	8
6.2	TEST AND MEASUREMENT EQUIPMENT	8
7	LINE CONDUCTED & RADIATED EMISSION TEST.....	11
7.1	LIMIT	11
7.2	TEST PROCEDURE OF LINE CONDUCTED EMISSION	12
7.3	TEST PROCEDURE OF COMMON MODE CONDUCTED EMISSION FOR TELECOMMUNICATION PORT	13
7.4	TEST PROCEDURE OF RADIATED EMISSION	14
7.5	TEST RESULTS	16
8	POWER HARMONICS TEST	20
9	POWER VOLTAGE FLUCTUATION / FLICKER TEST	22
10	ELECTROSTATIC DISCHARGE (ESD) IMMUNITY TEST	24
11	RADIATED ELECTROMAGNETIC FIELD IMMUNITY TEST	29
12	FAST TRANSIENTS/BURST IMMUNITY TEST	32
13	SURGE IMMUNITY TEST	34
14	CONDUCTED DISTURBANCE/INDUCED RADIO-FREQUENCY FIELD IMMUNITY TEST	36
15	POWER FREQUENCY MAGNETIC FIELD IMMUNITY TEST.....	38
16	VOLTAGE DIPS / SHORT INTERRUPTIONS	40
	APPENDIX I - PHOTOGRAPHS OF TEST SETUP	41



1 TEST RESULT CERTIFICATION

Applicant: Advantech Co., Ltd.
No. 1, Alley 20, Lane 26, Rueiguang Road, Neihu District,
Taipei 114, Taiwan, R.O.C.

Manufacturer: Advantech Co., Ltd.
No. 1, Alley 20, Lane 26, Rueiguang Road, Neihu District,
Taipei 114, Taiwan, R.O.C.

Equipment Under Test: Universal Network Controller

Trade Name: Advantech

Model: UNO-1019

Detailed EUT Description: See Item 2 of this report

Date of Test: October 18 ~ November 3, 2006

Applicable Standard	Class/Limit/Criterion	Test Result
EN 55022: 1998 + A1: 2000 + A2: 2003	Class A	No non-compliance noted
EN 61000-3-2: 2000	Class A/B/C/D	N/A
EN 61000-3-3: 1995 + A1: 2001	Limit	N/A
EN 55024: 1998 + A1: 2001 + A2: 2003, including		
IEC 61000-4-2: 1995 + A1: 1998 + A2: 2000 EN 61000-4-2: 1995 + A1: 1998 + A2: 2001	Criterion B	No non-compliance noted
IEC 61000-4-3: 2002 + A1: 2002 EN 61000-4-3: 2002 + A1: 2002	Criterion A	No non-compliance noted
IEC 61000-4-4: 1995 + A1: 2000 + A2: 2001 EN 61000-4-4: 1995 + A1: 2001 + A2: 2001	Criterion B	No non-compliance noted
IEC 61000-4-5: 1995 + A1: 2000 EN 61000-4-5: 1995 + A1: 2001	Criterion B	No non-compliance noted
IEC 61000-4-6: 1996 + A1: 2000 EN 61000-4-6: 1996 + A1: 2001	Criterion A	No non-compliance noted
IEC 61000-4-8: 1993 + A1: 2000 EN 61000-4-8: 1993 + A1: 2001	Criterion A	No non-compliance noted
IEC 61000-4-11: 1994 + A1: 2000 EN 61000-4-11: 1994 + A1: 2001	Criterion B/C/C	N/A
Deviation from Applicable Standard		
1. According to applicant's declaration this EUT is a class A product, and to be market in industrial environment only.		
2. The EN-Standards listed under EN 55024 are requested description by the applicant.		

The above equipment was tested by Compliance Certification Services Inc. for compliance with the requirements set forth in the EMC Directive 89/336/EEC, Amended by 92/31/EEC, 93/68/EEC and the technical standards mentioned above. The results of testing in this report apply only to the product/system, which was tested. Other similar equipment will not necessarily produce the same results due to production tolerance and measurement uncertainties.

Approved by:

Miller Lee
Deputy Manager of Linkou Laboratory
Compliance Certification Services Inc.

Reviewed by:

Susan Su
Section Manager of Linkou Laboratory
Compliance Certification Services Inc.



2 EUT DESCRIPTION

Product	Universal Network Controller		
Trade Name	Advantech		
Model	UNO-1019		
Housing Type	Plastic		
EUT Power Rating	10-30VDC from DC Power Supply		
CPU Manufacturer	Intel	Model	(R) PXA200MHz
Memory Capacity	64MB		
Com Adapter	N/A		

I/O PORT OF EUT

I/O PORT TYPE	Q'TY	TESTED WITH
1). LAN Port	2	2
2). COM Port	4	4



3 TEST METHODOLOGY

3.1 EUT SYSTEM OPERATION

1. The EUT was connected DC power source and connected with Host PC via HUB through Ethernet on remote side.
2. The internal program of EUT was executed.
3. A communicated software was loaded and executed to communicate between EUT and remote side.
4. EUT sends and received data from HUB and Host PC on remote side via LAN Cable.
5. Repeat 2 to 4.

Note: Test program is self-repeating throughout the test.

3.2 DECISION OF FINAL TEST MODE

1. The following test mode was scanned during the preliminary test:

Mode 1

Data transmit

2. After the preliminary scan, the following test mode was found to produce the highest emission level.

Mode 1

Then, the EUT configuration and cable configuration of the above highest emission mode was chosen for all final test items.



4 SETUP OF EQUIPMENT UNDER TEST

Setup Diagram

See test photographs attached in Appendix 1 for the actual connections between EUT and support equipment.

Support Equipment

No.	Equipment	Model No.	Serial No.	FCC ID	Trade Name	Data Cable	Power Cord
1.	DC Power Supply	GPS-3303	N/A	N/A	GW	Unshielded, 1.0m x 2	Unshielded, 1.5m
2.	HUB (Remote)	DS104	N/A	FCC DoC	NERGEAR	LAN Cable: Unshielded, 15m x 2	N/A
3.	Internet (Remote)	N/A	N/A	N/A	N/A	LAN Cable: Unshielded, 20m	N/A

Grounding: *Grounding was in accordance with the manufacturer's requirements and conditions for the intended use.*

5 FACILITIES AND ACCREDITATIONS

5.1 FACILITIES








All measurement facilities used to collect the measurement data are located at CCS Taiwan Linkou Lab at No. 81-1, Lane 210, Pa-De 2nd Rd., Luchu Hsiang, Taoyuan Shien, Taiwan.

The measurement facilities are constructed in conformance with the requirements of CISPR 16-1, ANSI C63.4 and other equivalent standards.

5.2 LABORATORY ACCREDITATIONS AND LISTINGS

The test facilities used to perform Electromagnetic compatibility tests are registered or accredited by the organizations listed in the following table which includes the recognized scope specifically.

This accredited organization maintains A2LA accreditation to ISO/IEC 17025 for the specific test listed in A2LA Certificate # 0824-01.

Country	Agency	Scope of Accreditation	Logo
USA	A2LA	EN 55011, EN 55014-1/2, CISPR 11, CISPR 14-1/2, EN 55022, EN 55015, CISPR 22, CISPR 15, AS/NZS 3548, VCCI V3 (2001), CFR 47, FCC Part 15/18, CNS 13783-1, CNS 13439, CNS 13438, CNS 13803, CNS 14115, EN 55024, IEC 801-2, IEC 801-3, IEC 801-4, IEC/EN 61000-3-2, IEC/EN 61000-3-3, IEC/EN 61000-4-2/3/4/5/6/8/11, EN 50081-1/EN 61000-6-3, EN 50081-2/EN 61000-6-4, EN 50081-2/EN 61000-6-1: 2001	 ACCREDITED No. 0824-01
USA	FCC	3/10 meter Open Area Test Sites to perform FCC Part 15/18 measurements	 93105, 90471
Japan	VCCI	3/10 meter Open Area Test Sites and conducted test sites to perform radiated/conducted measurements	 R-393/2316/725/1868 C-402/747/912
Norway	NEMKO	EN 50081-1/2, EN 50082-1/2, IEC 61000-6-1/2, EN 50091-2, EN 50130-4, EN 55011, EN 55013, EN 55014-1/2, EN 55015, EN 55022, EN 55024, EN 61000-3-2/3, EN 61326-1, IEC 61000-4-2/3/4/5/6/8/11, EN 60601-1-2, EN 300 328-2, EN 300 422-2, EN 301 419-1, EN 301 489-01/03/07/08/09/17, EN 301 419-2/3, EN 300 454-2, EN 301 357-2	 ELA 124a ELA 124b ELA 124c
Taiwan	TAF	EN 300 328-1, EN 300 328-2, EN 300 220-1, EN 300 220-2, EN 300 220-3, 47 CFR FCC Part 15 Subpart C, EN 61000-3-2, EN 61000-3-3, CNS 13439, CNS 13783-1, CNS 14115, CNS 13438, AS/NZS CISPR 22, CNS 13022-1, IEC 61000-4-2/3/4/5/6/8/11, CNS 13022-2/3	 Testing Laboratory 0363
Taiwan	BSMI	CNS 13438, CNS 13783-1, CNS 13439, CNS 14115	 SL2-IS-E-0014 / IN-E-0014 /A1-E-0014 /R1-E-0014 /R2-E-0014 /L1-E-0014
Canada	Industry Canada	RSS212, Issue 1	 IC 3991-3 IC 3991-4

Note: No part of this report may be used to claim or imply product endorsement by A2LA, TAF or other government agency.



6 INSTRUMENT AND CALIBRATION

6.1 MEASURING INSTRUMENT CALIBRATION

The measuring equipment utilized to perform the tests documented in this report has been calibrated once a year or in accordance with the manufacturer's recommendations, and is traceable under the IEC 17025 to international or national standards. Equipment has been calibrated by accredited calibration laboratories.

6.2 TEST AND MEASUREMENT EQUIPMENT

The following list contains measurement equipment used for testing. The equipment conforms to the requirement of CISPR 16-1, ANSI C63.2 and other required standards.

Calibration of all test and measurement, including any accessories that may effect such calibration, is checked frequently to ensure the accuracy. Adjustments are made and correction factors are applied in accordance with the instructions contained in the respective manual.

Equipment Used for Emission Measurement

Conducted Emission Test Site # 3				
Name of Equipment	Manufacturer	Model	Serial Number	Calibration Due
EMI Test Receiver	R&S	ESCS30	845552/030	03/21/2007
LISN	FCC	FCC-LISN-50/250-16-2-07	06012	10/08/2007
LISN	R&S	ESH2-Z5	843285/010	01/04/2007
ISN	FCC	FCC-TLISN-T4	20065	05/07/2007

Note: The measurement uncertainty is less than +/- 3.4509dB, which is evaluated as per the NAMAS NIS 81 and CISPR/A/291/CDV.

Open Area Test Site # 1				
Name of Equipment	Manufacturer	Model	Serial Number	Calibration Due
Spectrum Analyzer	ADVANTEST	R3261C	81720301	N.C.R
EMI Test Receiver	R&S	ESVS20	838804/004	01/18/2007
Pre-Amplifier	HP	8447D	2944A09173	03/22/2007
Bilog Antenna	Sunol Sciences	JB1	A111203	03/24/2007
Turn Table	EMCO	2081-1.21	N/A	N.C.R
Antenna Tower	EMCO	2075-2	9707-2604	N.C.R
Controller	EMCO	2090	N/A	N.C.R
RF Switch	Anritsu	MP59B	M54367	N.C.R
Site NSA	CCS	N/A	N/A	08/18/2007
DECOUPLING NETWORK	FCC	F-201-DCN-1-18MM	12	03/19/2007

Note: The measurement uncertainty is less than +/- 4.5272dB, which is evaluated as per the NAMAS NIS 81 and CISPR/A/291/CDV.



Power Harmonic & Voltage Fluctuation/Flicker Measurement (EN 61000-3-2&-3-3)				
Name of Equipment	Manufacturer	Model	Serial Number	Calibration Due
HARMONICS SYSTEM	EMC-PARTNER	HARMONICS -1000	094	11/22/2006

Equipment Used for Immunity Measurement

ESD Test Site (IEC/EN 61000-4-2)				
Name of Equipment	Manufacturer	Model	Serial Number	Calibration Due
ESD Generator	SCHAFFNER	NSG438	170	05/08/2007

Radiated Electromagnetic Field Immunity Test Site (IEC/EN 61000-4-3)				
Name of Equipment	Manufacturer	Model	Serial Number	Calibration Due
S.G.	R&S	SMY02	100094	08/13/2007
Power Meter	R&S	NRVD	837794/029	08/13/2007
Power Sensor	R&S	URV5-Z2	835640/015	08/13/2007
Power Sensor	R&S	URV5-Z2	835640/016	08/13/2007
Power Amplifier	ar	150W1000	300300	N.C.R

Fast Transients/Burst Test Site (IEC/EN 61000-4-4)				
Name of Equipment	Manufacturer	Model	Serial Number	Calibration Due
EMC TEST SYSTEM	EMC-PARTNER	TRANSIENT -2000	754	09/14/2007
Clamp	HAEFELY TRENCH	093 506.1	080 421.13	N.C.R

Surge Immunity Test Site (IEC/EN 61000-4-5)				
Name of Equipment	Manufacturer	Model	Serial Number	Calibration Due
Surge Tester	HAEFELY TRENCH	PSUGER 4010	583 334-71	09/04/2007



CS Test Site (IEC/EN 61000-4-6)				
Name of Equipment	Manufacturer	Model	Serial Number	Calibration Due
S.G.	R&S	SMY02	100094	08/13/2007
Power Meter	R&S	NRVD	837794/029	08/13/2007
Power Sensor	R&S	URV5-Z2	835640/015	08/13/2007
Power Sensor	R&S	URV5-Z2	835640/016	08/13/2007
Power Amplifier	ar	500A100A	300299	N.C.R
CDN	FCC	FCC-801-M3-16A	99122	08/31/2007
CDN	Lüthi	801-M3	1879	N.C.R.
CDN	SCHAFFNER	T400	16906	12/28/2006

Power Frequency Magnetic Field Immunity Test Site (IEC/EN 61000-4-8)				
Name of Equipment	Manufacturer	Model	Serial Number	Calibration Due
TRIAX ELF Magnetic Field Meter	F.W.BELL	4090	9711	11/27/2006
Clamp Meter	National	300K	11-5980 K	11/22/2006
Magnetic Field Tester	HAEFELY TRENCH	MAG 100.1	080 938-01	05/17/2007

7 LINE CONDUCTED & RADIATED EMISSION TEST

7.1 LIMIT

Maximum permissible level of Line Conducted Emission

Frequency (MHZ)	Class A (dBuV)		Class B (dBuV)	
	Quasi-peak	Average	Quasi-peak	Average
0.15 - 0.5	79	66	66 - 56	56 - 46
0.50 - 5.0	73	60	56	46
5.0 - 30.0	73	60	60	50

Note: The lower limit shall apply at the transition frequency.

Maximum permissible level of Common Mode Conducted Emission (Telecommunication Ports)

CLASS A

Frequency (MHZ)	Voltage Limit (dBuV)		Current Limit (dBuA)	
	Quasi-peak	Average	Quasi-peak	Average
0.15 - 0.5	97 – 87	84 - 74	53 – 43	40 – 30
0.5 - 30.0	87	74	43	30

Note: The lower limit shall apply at the transition frequency.

CLASS B

Frequency (MHZ)	Voltage Limit (dBuV)		Current Limit (dBuA)	
	Quasi-peak	Average	Quasi-peak	Average
0.15 - 0.5	84 - 74	74 - 64	40 – 30	30 – 20
0.5 - 30.0	74	64	30	20

Note: The lower limit shall apply at the transition frequency.

Maximum permissible level of Radiated Emission measured at 10 meter

Frequency (MHZ)	Class A (dBuV/m)	Class B (dBuV/m)
	Quasi-peak	Quasi-peak
30 – 230	40	30
230 - 1000	47	37

Note: The lower limit shall apply at the transition frequency.



7.2 TEST PROCEDURE OF LINE CONDUCTED EMISSION

Procedure of Preliminary Test

- The EUT was set up as per the test configuration to simulate typical usage per the user's manual. When the EUT is a tabletop system, a wooden table with a height of 0.8 meters is used and is placed on the ground plane as per EN 55022 (see Test Facility for the dimensions of the ground plane used). When the EUT is a floor-standing equipment, it is placed on the ground plane which has a 3-12 mm non-conductive covering to insulate the EUT from the ground plane.
- Support equipment, if needed, was placed as per EN 55022.
- All I/O cables were positioned to simulate typical actual usage as per EN 55022.
- The test equipment EUT installed received AC power, 230VAC/50Hz, through a Line Impedance Stabilization Network (LISN), which supplied power source and was grounded to the ground plane.
- All support equipment received power from a second LISN.
- The EUT test program was started. Emissions were measured on each current carrying line of the EUT using an EMI Test Receiver connected to the LISN powering the EUT.
- The Receiver scanned from 150kHz to 30MHz for emissions in each of the test modes.
- During the above scans, the emissions were maximized by cable manipulation.
- The test mode(s) described in Item 3.2 were scanned during the preliminary test.
- After the preliminary scan, we found the test mode described in Item 3.2 producing the highest emission level.
- The worst configuration of EUT and cable of the above highest emission level were recorded for reference of the final test.

Procedure of Final Test

- EUT and support equipment were set up on the test bench as per the configuration with highest emission level in the preliminary test.
- A scan was taken on both power lines, Line 1 and Line 2, recording at least the six highest emissions. Emission frequency and amplitude were recorded into a computer in which correction factors were used to calculate the emission level and compare reading to the applicable limit. If EUT emission level was less -2dB to the Average limit in Q.P. mode, then the emission signal was re-checked using an Average detector.
- The test data of the worst-case condition(s) was recorded.

**Data Sample:**

Frequency (MHz)	QuasiPeak reading (dBuV)	Average reading (dBuV)	Correctrion factor (dB)	QuasiPeak result (dBuV)	Average result (dBuV)	QuasiPeak. limit (dBuV)	Average limit (dBuV)	QuasiPeak margin (dB)	Average margin (dB)	Remark
x.xx	43.95	33	10.0	53.95	43	56.00	46.00	-2.05	-3	Pass

Frequency (MHz) = Emission frequency in MHz

Reading (dBuV) = Uncorrected Analyzer/Receiver reading + Insertion loss of LISN, if it > 0.5 dB

Correction Factor (dB) = Antenna factor + Cable loss – Amplifier gain

Result (dBuV) = Raw reading converted to dBuV and CF added

Limit (dBuV) = Limit stated in standard

Margin (dB) = Result (dBuV) – Limit (dBuV)

7.3 TEST PROCEDURE OF COMMON MODE CONDUCTED EMISSION FOR TELECOMMUNICATION PORT

- Selecting ISN for unscreened cable or a current probe for screened cable to take measurement.
- The port of the EUT was connected to the remote side support equipment through the ISN/Current Probe and communication in normal condition.
- Making a overall range scan by using the test receiver controlled by controller and record at least six highest emissions for showing in the test report.
- Emission frequency and amplitude were recorded into a computer in which correction factors were used to calculate the emission level and compare reading to the applicable limit.
- In case of measuring on the screened cable, the current limit shall be applied, otherwise the voltage limit should be applied.
- The following test mode was scanned during the preliminary test:

No applicable, the conducted emission test item for telecom ports disturbance voltage is not tested in this report as per client's request.

**Data Sample:**

Frequency (MHz)	QuasiPeak reading (dBuV)	Average reading (dBuV)	Correction factor (dB)	QuasiPeak result (dBuV)	Average result (dBuV)	QuasiPeak limit (dBuV)	Average limit (dBuV)	QuasiPeak margin (dB)	Average margin (dB)	Remark
x.xx	43.95	33	10.0	53.95	43	74.00	64.00	-20.05	-21	Pass

Frequency (MHz) = Emission frequency in MHz

Reading (dBuV) = Uncorrected Analyzer/Receiver reading + Insertion loss of LISN, if it > 0.5 dB

Correction Factor (dB) = Antenna factor + Cable loss – Amplifier gain

Result (dBuV) = Raw reading converted to dBuV and CF added

Limit (dBuV) = Limit stated in standard

Margin (dB) = Result (dBuV) – Limit (dBuV)

7.4 TEST PROCEDURE OF RADIATED EMISSION

Procedure of Preliminary Test

- The equipment was set up as per the test configuration to simulate typical usage per the user's manual. When the EUT is a tabletop system, a wooden turntable with a height of 0.8 meters is used which is placed on the ground plane. When the EUT is a floor-standing equipment, it is placed on the ground plane which has a 3-12 mm non-conductive covering to insulate the EUT from the ground plane.
- Support equipment, if needed, was placed as per EN 55022.
- All I/O cables were positioned to simulate typical usage as per EN 55022.
- The EUT received AC power source, 230VAC/50Hz, from the outlet socket under the turntable. All support equipment received power from another socket under the turntable.
- Mains cables, telephone lines or other connections to auxiliary equipment located outside the test are shall drape to the floor, be fitted with ferrite clamps or ferrite tubes placed on the floor at the point where the cable reaches the floor and then routed to the place where they leave the turntable. No. extension cords shall be used to mains receptacle.
- The antenna was placed at 10 meter away from the EUT as stated in EN 55022. The antenna connected to the Spectrum Analyzer via a cable and at times a pre-amplifier would be used.
- The Analyzer / Receiver quickly scanned from 30MHz to 1000MHz. The EUT test program was started. Emissions were scanned and measured rotating the EUT to 360 degrees and positioning the antenna 1 to 4 meters above the ground plane, in both the vertical and the horizontal polarization, to maximize the emission reading level.
- The test mode(s) described in Item 3.2 were scanned during the preliminary test:
- After the preliminary scan, we found the test mode described in Item 3.2 producing the highest emission level.
- The worst configuration of EUT and cable, antenna position, polarization and turntable position of the above highest emission level were recorded for the final test.

**Procedure of Final Test**

- EUT and support equipment were set up on the turntable as per the configuration with highest emission level in the preliminary test.
- The Analyzer / Receiver scanned from 30MHz to 1000MHz. Emissions were scanned and measured rotating the EUT to 360 degrees, varying cable placement and positioning the antenna 1 to 4 meters above the ground plane, in both the vertical and the horizontal polarization, to maximize the emission reading level.
- Recorded at least the six highest emissions. Emission frequency, amplitude, antenna position, polarization and turntable position were recorded into a computer in which correction factors were used to calculate the emission level and compare reading to the applicable limit and only Q.P. reading is presented.
- The test data of the worst-case condition(s) was recorded.

Data Sample:

Frequency (MHz)	Reading (dBuV)	Correction Factor (dB/m)	Result (dBuV/m)	Limit (dBuV/m)	Margin (dB)	Degree (°)	Height (cm)	Remark
xx.xx	16.49	9.86	26.35	30.00	-3.65	116.00	101.00	QP

Frequency (MHz) = Emission frequency in MHz
Reading (dBuV) = Uncorrected Analyzer / Receiver reading
Correction Factor (dB/m) = Antenna factor + Cable loss – Amplifier gain
Result (dBuV/m) = Reading (dBuV) + Corr. Factor (dB/m)
Limit (dBuV/m) = Limit stated in standard
Margin (dB) = Result (dBuV/m) – Limit (dBuV/m)
Q.P. = Quasi-Peak



7.5 TEST RESULTS

Line Conducted Emission

Model: N/A

Test Mode: N/A

Temperature: N/A

Humidity: N/A


Tested by: N/A

Test Results: N/A

****Note: This EUT has not connection to AC Source direct. No applicable for this test.**

**Common Mode Conducted Emission****Linkou Conduction 3**


Job No.:	60926106	Line:	ISN4
Standard:	EN55022 ISN Class A		
Test Item:	Conduction Emission	Date:	2006/10/18
Temp.(°C)/Hum.(%RH):	24°C/46%RH	Time:	PM 12:22
Company:	ADVANTECH	Tested By:	Michael Chen
Model:	UNO-1019	Test Mode:	1



NO.	Frequency	QuasiPeak reading	Average reading	Correction factor	QuasiPeak result	Average result	QuasiPeak limit	Average limit	QuasiPeak margin	Average margin	Remark
	(MHz)	(dBuV)	(dBuV)	(dB)	(dBuV)	(dBuV)	(dBuV)	(dBuV)	(dB)	(dB)	(Pass/Fail)
1	0.21	67.53	67.08	20.45	87.98	87.53	95.29	82.29	-7.30	5.25	Fail
2	0.41	61.38	61.52	20.43	81.81	81.95	89.46	76.46	-7.65	5.49	Fail
3	0.62	53.32	51.97	20.41	73.73	72.38	87.00	74.00	-13.27	-1.62	Pass
4	13.42	49.28	46.49	20.21	69.49	66.70	87.00	74.00	-17.51	-7.30	Pass
5	23.13	53.57	51.02	20.20	73.77	71.22	87.00	74.00	-13.23	-2.78	Pass
6	26.61	51.79	49.17	20.21	72.00	69.38	87.00	74.00	-15.00	-4.62	Pass

**Radiated Emission (A)****CCS Radiated Test OATS 1**


Job No.:	60926106	Ant. Polar.:	Ver.
Standard:	EN 55022 Class A	Tested Distance:	10m
Test Item:	Radiated Emission	Date:	2006/11/3
Temp.(°C)/Hum.(%RH):	26°C/55%RH	Time:	PM 02:10
Company:	ADVANTECH	Tested By:	Michael Chen
Model:	UNO-1019	Test Mode:	1



No.	Frequency (MHz)	Reading (dBuV)	Correction Factor (dB/m)	Result (dBuV/m)	Limit (dBuV/m)	Margin (dB)	Degree (°)	Height (cm)	Remark
1	125.00	22.00	10.65	32.65	40.00	-7.35	0.00	100.00	QP
2	174.86	19.00	10.88	29.88	40.00	-10.12	0.00	100.00	QP
3	200.17	19.10	12.30	31.40	40.00	-8.60	0.00	100.00	QP
4	212.00	20.00	12.76	32.76	40.00	-7.24	0.00	100.00	QP
5	575.00	14.90	21.72	36.62	47.00	-10.38	0.00	100.00	QP
6	775.00	12.90	24.01	36.91	47.00	-10.09	0.00	100.00	QP

**Radiated Emission (B)****CCS Radiated Test OATS 1**

Job No.:	60926106	Ant. Polar.:	Hor.
Standard:	EN 55022 Class A	Tested Distance:	10m
Test Item:	Radiated Emission	Date:	2006/11/3
Temp.(°C)/Hum.(%RH):	26°C/55%RH	Time:	PM 01:51
Company:	ADVANTECH	Tested By:	Michael Chen
Model:	UNO-1019		



No.	Frequency (MHz)	Reading (dBuV)	Correction Factor (dB/m)	Result (dBuV/m)	Limit (dBuV/m)	Margin (dB)	Degree (°)	Height (cm)	Remark
1	125.00	18.50	10.65	29.15	40.00	-10.85	0.00	100.00	QP
2	174.89	18.50	10.89	29.39	40.00	-10.61	0.00	100.00	QP
3	200.20	16.50	12.30	28.80	40.00	-11.20	0.00	100.00	QP
4	225.00	16.90	13.27	30.17	40.00	-9.83	0.00	100.00	QP
5	575.00	13.80	21.72	35.52	47.00	-11.48	0.00	100.00	QP
6	675.00	13.40	22.83	36.23	47.00	-10.77	0.00	100.00	QP



8 POWER HARMONICS TEST

Port : AC mains

Basic Standard : EN 61000-3-2

Limits : ☐ CLASS A ; ☐ CLASS B ; ☐ CLASS C ; ☐ CLASS D

Tested by : N/A


Temperature : N/A

Humidity : N/A

Limit:

Limits for Class A equipment	
Harmonics Order n	Max. permissible harmonics current A
Odd harmonics	
3	2.30
5	1.14
7	0.77
9	0.40
11	0.33
13	0.21
15<=n<=39	0.15x15/n
Even harmonics	
2	1.08
4	0.43
6	0.30
8<=n<=40	0.23x8/n

Limits for Class D equipment		
Harmonics Order n	Max. permissible harmonics current per watt mA/W	Max. permissible harmonics current A
Odd Harmonics only		
3	3.4	2.30
5	1.9	1.14
7	1.0	0.77
9	0.5	0.40
11	0.35	0.33
13	0.30	0.21
15<=n<=39	3.85/n	0.15x15/n

Block Diagram of Test Setup:**Test Procedure:**

- a. The EUT was placed on the top of a wooden table 0.8 meters above the ground and operated to produce the maximum harmonic components under normal operating conditions for each successive harmonic component in turn.
- b. The correspondent test program of test instrument to measure the current harmonics emanated from EUT is chosen. The measure time shall be not less than the time necessary for the EUT to be exercised.

Test Result : (See Appendix II for details)

Not applicable, because EUT not connect to AC Main Source direct.


9 POWER VOLTAGE FLUCTUATION / FLICKER TEST

Port : AC mains
Basic Standard : EN 61000-3-3
Limits : §5 of EN 61000-3-3
Tested by : N/A
Temperature : N/A
Humidity : N/A

Limit:

TEST ITEM	LIMIT	REMARK
P_{st}	1.0	P_{st} means short-term flicker indicator.
P_{lt}	0.65	P_{lt} means long-term flicker indicator.
T_{dt} (ms)	500	T_{dt} means maximum time that dt exceeds 3 %.
d_{max} (%)	4%	d_{max} means maximum relative voltage change.
dc (%)	3.3%	dc means relative steady-state voltage change

Block Diagram of Test Setup:





Test Procedure:

- a. The EUT was placed on the top of a wooden table 0.8 meters above the ground and operated to produce the most unfavorable sequence of voltage changes under normal operating conditions.
- b. During the flick measurement, the measure time shall include that part of whole operation cycle in which the EUT produce the most unfavorable sequence of voltage changes. The observation period for short-term flicker indicator is 10 minutes and the observation period for long-term flicker indicator is 2 hours.

Test Result:


Not applicable, because EUT not connect to AC Main Source direct.

10 ELECTROSTATIC DISCHARGE (ESD) IMMUNITY TEST

Port	: Enclosure
Basic Standard	: IEC/EN 61000-4-2
Test Level	: ± 8 kV (Air Discharge) ± 4 kV (Contact Discharge) ± 4 kV (Indirect Discharge)
Performance Criterion	: B (Standard Required)
Tested by	: Michael Chen
Temperature	: 24°C
Humidity	: 46% RH
Pressure	: 1006mbar

Block Diagram of Test Setup:

(The 470 k ohm resistors are installed per standard requirement.)



**Test Procedure:**

1. The Host PC (included EUT) was located 0.1 m minimum from all side of the HCP.
2. The indirect support units were located 1 m minimum away from the EUT, but direct support unit was/were located at same location as EUT on the HCP and keep at a distance of 10 cm with EUT.
3. A scroll 'H' test program was loaded and executed in Windows XP mode.
4. The Host PC (included EUT) sent above message to monitor and related peripherals through the test.
5. Active the communication function if the EUT with such port(s).
6. As per the requirement of EN 55024; applying direct contact discharge at the sides other than front of EUT at minimum 50 discharges (25 positive and 25 negative) if applicable, can't be applied direct contact discharge side of EUT then the indirect discharge shall be applied. One of the test points shall be subjected to at least 50 indirect discharge (contact) to the front edge of horizontal coupling plane.
7. Other parts of EUT where it is not possible to perform contact discharge then selecting appropriate points of EUT for air discharge, a minimum of 10 single air discharges shall be applied.
8. The application of ESD to the contact of open connectors is not required.
9. The EUT direct connection units also need to be applied ESD at the port of EUT cable connected.
10. Putting a mark on EUT to show tested points. The following test condition was followed during the tests.

Note: As per IEC/EN 61000-4-2, two 470k bleed resistors cable is connected between the EUT and HCP during the test applicable for power ungrounded or battery operating unit only.

The electrostatic discharges were applied as follows:

Amount of discharge	Voltage	Coupling	Result (Pass/Fail)
Mini 10 /Point	± 8 kV	Air Discharge	Pass
Mini 25 /Point	± 4 kV	Contact Discharge	Pass
Mini 25 /Point	± 4 kV	Indirect Discharge HCP	Pass
Mini 25 /Point	± 4 kV	Indirect Discharge VCP (Right)	Pass
Mini 25 /Point	± 4 kV	Indirect Discharge VCP (Left)	Pass

For the tested points to EUT, please refer to attached page.

(Blue arrow mark for Contact Discharge and red arrow mark for Air Discharge)



Performance & Result:

- ☐ **Criteria A:** The apparatus continues to operate as intended. No degradation of performance or loss of function is allowed below a performance level specified by the manufacturer, when the apparatus is used as intended. In some cases the performance level may be replaced by a permissible loss of performance.
- ☒ **Criteria B:** The apparatus continues to operate as intended after the test. No degradation of performance or loss of function is allowed below a performance level specified by the manufacturer, when the apparatus is used as intended. In some cases the performance level may be replaced by a permissible loss of performance. During the test, degradation of performance is however allowed.
- ☐ **Criteria C:** Temporary loss of function is allowed, provided the functions self recoverable or can be restored by the operation of controls.



PASS



FAIL

Observation: The LAN Port were delayed communicate, but can be auto recovered as the events disappear.

The Tested Points of EUT

Photo 1 of 3



Photo 2 of 3





Photo 3 of 3



11 RADIATED ELECTROMAGNETIC FIELD IMMUNITY TEST

Port : Enclosure

Basic Standard : IEC/EN 61000-4-3

Requirements : 3 V/m / with 80% AM. 1kHz Modulation.

Performance Criterion : A (Standard Required)


Tested by : Michael Chen

Temperature : 26°C

Humidity : 59% RH

Pressure : 1001mbar

Block Diagram of Test Setup:



**Test Procedure:**

1. The EUT was located at the edge of supporting table keep 3 meter away from transmitting antenna, it just the calibrated square area of field uniformity. The support units were located outside of the uniformity area, but the cable(s) connected with EUT were exposed to the calibrated field as per IEC/EN 61000-4-3.
2. Setting the testing parameters of RS test software per IEC/EN 61000-4-3.
3. From the result of pre-test in step 5, choice the worst side of EUT for final test from 80 MHz to 1000 MHz at 1% steps.
4. Recording the test result in following table.

Test Results:

Test level : 3V/m
Steps : 1 % of fundamental
Dwell Time : 3 sec

Frequency (MHz)	Polarity	Azimuth	Field Strength (V/m)	Observation	Result
80 ~ 1000	V&H	0	3	Note	PASS
80 ~ 1000	V&H	90	3	Note	PASS
80 ~ 1000	V&H	180	3	Note	PASS
80 ~ 1000	V&H	270	3	Note	PASS



Performance & Result:

- ☒ **Criteria A:** The apparatus continues to operate as intended. No degradation of performance or loss of function is allowed below a performance level specified by the manufacturer, when the apparatus is used as intended. In some cases the performance level may be replaced by a permissible loss of performance.
- ☐ **Criteria B:** The apparatus continues to operate as intended after the test. No degradation of performance or loss of function is allowed below a performance level specified by the manufacturer, when the apparatus is used as intended. In some cases the performance level may be replaced by a permissible loss of performance. During the test, degradation of performance is however allowed.
- ☐ **Criteria C:** Temporary loss of function is allowed, provided the functions self recoverable or can be restored by the operation of controls.

☒ **PASS** ☐ **FAIL**

Observation: No function degraded during the tests.

12 FAST TRANSIENTS/BURST IMMUNITY TEST

Port : On Power Supply Line and LAN Cable

Basic Standard : IEC/EN 61000-4-4

Requirements : ± 1 kV for Power Supply Line
 ± 0.5 kV for LAN Cable

Performance Criteria : B (Standard Required)


Tested by : Michael Chen

Temperature : 25°C

Humidity : 50% RH

Pressure : 1001mbar

Block Diagram of Test Setup:



Test Procedure:

1. The EUT and support units were located on a wooden table 0.8 m away from ground reference plane.
2. A 1.0 meter long power cord was attached to EUT during the test.
3. The length of communication cable between communication port and clamp was keeping within 1 meter.
4. Injected test voltage to the EUT ports from minimum to standard request or client request.
5. Recording the test result as shown in following table.

**Test conditions:**

Impulse Frequency : 5kHz
Tr/Th : 5/50ns
Burst Duration : 15ms
Burst Period : 3Hz

Inject Line	Voltage kV	Inject Method	Result (Pass/Fail)
L	± 1	Direct	Pass
N	± 1	Direct	Pass
L + N	± 1	Direct	Pass
RJ 45 Port (LAN Cable)	± 0.5	Clamp	Pass

Performance & Result:

- ☒ **Criteria A:** The apparatus continues to operate as intended. No degradation of performance or loss of function is allowed below a performance level specified by the manufacturer, when the apparatus is used as intended. In some cases the performance level may be replaced by a permissible loss of performance.
- ☐ **Criteria B:** The apparatus continues to operate as intended after the test. No degradation of performance or loss of function is allowed below a performance level specified by the manufacturer, when the apparatus is used as intended. In some cases the performance level may be replaced by a permissible loss of performance. During the test, degradation of performance is however allowed.
- ☐ **Criteria C:** Temporary loss of function is allowed, provided the functions self recoverable or can be restored by the operation of controls.

☒ **PASS** ☐ **FAIL**

Observation: No function degraded during the tests.

13 SURGE IMMUNITY TEST

Port : Power Cord

Basic Standard : IEC/EN 61000-4-5

Requirements : ± 1 kV (Line to Line)

Performance Criteria : B (Standard Required)


Tested by : Michael Chen

Temperature : 25°C

Humidity : 54% RH

Pressure : 1003mbar

Block Diagram of Test Setup:



Test Procedure:

1. The EUT and support units were located on a wooden table 0.8 m away from ground floor.
2. Injected test voltage to the EUT ports from minimum to standard request or client request.
3. Recording the test result as shown in following table.

**Test conditions:**

Voltage Waveform : 1.2/50 μ s
Current Waveform : 8/20 μ s
Polarity : Positive/Negative
Phase angle : 0°, 90°, 270°
Number of Test : 5

Coupling Line	Voltage (kV)	Polarity	Coupling Method	Result (Pass/Fail)
L1-L2	1	Positive	Capacitive	Pass
L1-L2	1	Negative	Capacitive	Pass

Performance & Result:

- ☒ **Criteria A:** The apparatus continues to operate as intended. No degradation of performance or loss of function is allowed below a performance level specified by the manufacturer, when the apparatus is used as intended. In some cases the performance level may be replaced by a permissible loss of performance.
- ☐ **Criteria B:** The apparatus continues to operate as intended after the test. No degradation of performance or loss of function is allowed below a performance level specified by the manufacturer, when the apparatus is used as intended. In some cases the performance level may be replaced by a permissible loss of performance. During the test, degradation of performance is however allowed.
- ☐ **Criteria C:** Temporary loss of function is allowed, provided the functions self recoverable or can be restored by the operation of controls.

☒ **PASS** ☐ **FAIL**


Observation: No function degraded during the tests.

14 CONDUCTED DISTURBANCE/INDUCED RADIO-FREQUENCY FIELD IMMUNITY TEST


Port	: AC Port and LAN Cable
Basic Standard	: IEC/EN 61000-4-6
Requirements	: 3 V with 80% AM. 1kHz Modulation.
Injection Method	: CDN-M2 for Power Cord CDN-T4 for LAN Cable
Performance Criterion	: A (Standard Required)
Tested by	: Michael Chen
Temperature	: 26°C
Humidity	: 59% RH
Pressure	: 1001mbar

Block Diagram of Test Setup:

Side View:



Top View:



**Test Procedure:**

1. The EUT and support units were located at a ground reference plane with the interposition of a 0.1 m thickness insulating support and the CDN was located on GRP directly.
2. Setting the testing parameters of CS test software as per IEC/EN 61000-4-6.
3. Recording the test result in following table.

Test conditions:

Frequency Range : 0.15MHz-80MHz

Frequency Step : 1% of fundamental

Dwell Time : 3 sec

Range (MHz)	Field	Modulation	Result (Pass/Fail)
0.15-80	3V	Yes	Pass

Performance & Result:


- ☒ **Criteria A:** The apparatus continues to operate as intended. No degradation of performance or loss of function is allowed below a performance level specified by the manufacturer, when the apparatus is used as intended. In some cases the performance level may be replaced by a permissible loss of performance.
- ☐ **Criteria B:** The apparatus continues to operate as intended after the test. No degradation of performance or loss of function is allowed below a performance level specified by the manufacturer, when the apparatus is used as intended. In some cases the performance level may be replaced by a permissible loss of performance. During the test, degradation of performance is however allowed.
- ☐ **Criteria C:** Temporary loss of function is allowed, provided the functions self recoverable or can be restored by the operation of controls.

☒ **PASS** ☐ **FAIL****Observation:** No function degraded during the tests.

15 POWER FREQUENCY MAGNETIC FIELD IMMUNITY TEST

Port : Enclosure
Basic Standard : IEC/EN 61000-4-8
Requirements : 1 A/m
Performance Criterion : A (Standard Required)
Tested by : Michael Chen
Temperature : 25°C
Humidity : 54% RH
Pressure : 1003mbar

Block Diagram of Test Setup:



Test Procedure:

1. The EUT and support units were located on Ground Reference Plane with the interposition of a 0.1 m thickness insulation support.
2. Putting the induction coil on horizontal direction. (X direction)
3. Rotating the induction coil by 90° (Y direction)
4. Rotating the induction coil by 90° again (Z direction)
5. Recording the test result as shown in following table.

**Test conditions:**

Field Strength: 1A/m
Power Freq.: 50Hz
Orientation: X, Y, Z

Orientation	Field	Result (Pass/Fail)	Remark
X	1A/m	Pass	
Y	1A/m	Pass	
Z	1A/m	Pass	

Performance & Result:

- ☒ **Criteria A:** The apparatus continues to operate as intended. No degradation of performance or loss of function is allowed below a performance level specified by the manufacturer, when the apparatus is used as intended. In some cases the performance level may be replaced by a permissible loss of performance.
- ☐ **Criteria B:** The apparatus continues to operate as intended after the test. No degradation of performance or loss of function is allowed below a performance level specified by the manufacturer, when the apparatus is used as intended. In some cases the performance level may be replaced by a permissible loss of performance. During the test, degradation of performance is however allowed.
- ☐ **Criteria C:** Temporary loss of function is allowed, provided the functions self recoverable or can be restored by the operation of controls.

☒ **PASS** ☐ **FAIL**

Observation: No function degraded during the tests.



16 VOLTAGE DIPS / SHORT INTERRUPTIONS

Port : AC mains

Basic Standard : IEC/EN 61000-4-11

Requirement : PHASE ANGLE 0, 45, 90, 135, 180, 225, 270, 315 degrees

Test Interval : Min. 10 sec.

Tested by : N/A

Temperature : N/A

Humidity : N/A

Pressure : N/A

Performance & Result:

- Criteria A:** The apparatus continues to operate as intended. No degradation of performance or loss of function is allowed below a performance level specified by the manufacturer, when the apparatus is used as intended. In some cases the performance level may be replaced by a permissible loss of performance.
- Criteria B:** The apparatus continues to operate as intended after the test. No degradation of performance or loss of function is allowed below a performance level specified by the manufacturer, when the apparatus is used as intended. In some cases the performance level may be replaced by a permissible loss of performance. During the test, degradation of performance is however allowed.
- Criteria C:** Temporary loss of function is allowed, provided the functions self recoverable or can be restored by the operation of controls.

☐ **PASS** ☐ **FAIL**

Not applicable, because EUT not connect to AC Main Source direct.

APPENDIX I - PHOTOGRAPHS OF TEST SETUP

RADIATED EMISSION TEST (EN 55022)



ELECTROSTATIC DISCHARGE TEST





RADIATED ELECTROMAGNETIC FIELD TEST



FAST TRANSIENTS/BURST TEST





SURGE IMMUNITY TEST



CONDUCTED DISTURBANCE, INDUCED BY RADIO-FREQUENCY FIELDS TEST



POWER FREQUENCY MAGNETIC FIELD IMMUNITY TEST

